



REPUBLIKA NG PILIPINAS
Pambansang Korporasyon Sa Elektrisidad
 (NATIONAL POWER CORPORATION)
SMALL POWER UTILITIES GROUP - MINDANAO
PURCHASE ORDER

P.O. 008428(SVP)
 Page 1 of 1
 This PO number must appear on all papers, invoices, packing list and correspondence.

TO:
GEVANS CONSTRUCTION AND SUPPLY
 Rizal Street, Brgy. Washington Surigao City

DATE: July 04, 2022
PD NO.: S3-HKD22-013
PR DATE: February 11, 2022

DELIVERY PERIOD: WITHIN **30** CALENDAR DAYS FROM DATE OF RECEIPT OF THIS ORDER

TERMS: 30 DAYS UPON DELIVERY AND SUBMISSION OF ALL DOCUMENTS STATED AT THE BACK HEREOF / COD / PREPAYMENT

DELIVERY POINT:
PLANT SITE- HIKDOP DPP

REQUISITIONER:
R. U. FULLIDO / Div. Mgr. - EMOD

| PO ITEM NO. | PR NO./ ITEM NO. | DESCRIPTION | QTY | UNIT OF MEASURE | UNIT PRICE (P) | AMOUNT (P) | |
|--|------------------|--|-----|-----------------|----------------|------------|--|
| 1 | 1 | REPAIR OF POWERHOUSE & OTHER PLANT ACCESSORIES (POLES, POWER CABLE TRANSF ROOFINGS & CEILING REPAIR OF POWER PLANT & ACCESSORIES | 1 | LOT | | 825,892.86 | |
| SCOPE OF WORKS: A. PLANT PERIMETER FENCE 1. Pull-out and replace perimeter fence cyclone by forty-five (45) 467cm x 122cm steel mating, 1 ½ inch. G.I. pipe. 2. Painting of 20,574cm x 91 perimeter fence (Macaroon Cream) & its steel mating (Steel Grey). 3. Install perimeter fence round ball post lamp, LED, 16watts, #AWG, 8boxes (100m/box) and switches. B. SUBSTATION AND IT'S PERIMETER FENCE 4. Realignment of plant substation take-off structure 5. Pull-out and replace substation perimeter fence cyclone by steel mating, Three (3) 305cm x 122cm, Three (3) 336cm x 122cm, one (1) 366cm x 122cm, two (2) 396cm x 122cm, one (1) 244cm x 183cm and one (1) 92cm x 183cm and 1 ½ inch. G.I. pipe 6. Install six (6) perimeter round ball post lamp, LED, 16Watts, #14AWG, 2boxes (100m/box) and switches. 7. Painting of substation perimeter fence (3,414cm x 92cm) (Macaroon Cream) & its steel mating (Steel Grey). C. CONTROL ROOM 8. Installation of ceiling. Ceiling area 300cm x 800cm. 9. Installation of 6 pieces LED bulb 16Watts, electrical wirings (2box 14AWG stranded), switches and other electrical works. 10. Control room painting works (white color), 108sq. m. 11. Pull-out of existing two (3) 174cm x 134cm and replace by four (6) 87cm x 134cm control room tinted glass panel sliding windows. 12. Replace and install new two (2) 194cm x 73cm door with doorknob. 13. Installation of 40cm x 40cm floor tiles in 300cm x 800cm control room. D. POWERHOUSE 14. Pull-out of remaining G.I. corrugated roof sheets and replace corrugated color roof 15. Install electrical wiring, switches & ten (10) 18 Watts bulbs. 16. Repainting of wall (260sq.m), and rubberized paint (green) on floor (110sq.m). E. OFFICE/STAFFHOUSE 17. Installation of 12pieces 16Watts LED bulbs and wirings. 18. Repainting of internal and external wall and ceiling. 19. Repair off staff house lobby. 20. Install 40cm x 40cm garage tile on 300cm x 800cm staff house lobby. 21. Housekeeping. | | | | | | | |
| TOTAL COST OF GOODS.....P | | | | | | 825,892.86 | |
| TAX 12 % | | | | | | 99,107.14 | |
| TOTAL AMOUNT.....P | | | | | | 925,000.00 | |

ADDITIONAL TERMS & CONDITION

- Delivery shall be accompanied with Certificate of Warranty.
- Upon acceptance, a warranty shall be required either by retention money or special bank guarantee equivalent to Five percent (5%) of the contract price.

THIS ORDER IS SUBJECT TO THE TERMS & CONDITIONS PRINTED AT THE BACK HEREOF:

| | | | | | | |
|--|----|----|----|----|--|--|
| CC | GL | OE | WO | JO | Pambansang Korporasyon Sa Elektrisidad | Please signify your acceptance and agreement with this P.O. By signing below: |
| 6681036 513 676 F254753 FUNDS AVAILABLE ANNABELLE E. OGA Financial Specialist | | | | | BY YACOB H. DARAYAN Department Manager, SPUG-MOD AUTHORIZED SIGNATURE | CONFORME: SHAIN OLIVER V. IAMAYO POSITION: _____ DATE: <u>7-5-22</u> |