

# REPUBLIC OF THE PHILIPPINES NATIONAL POWER CORPORATION

(Pambansang Korporasyon sa Elektrisidad)

# **BID DOCUMENTS**

Name of Project : SUPPLY, DELIVERY, INSTALLATION, TESTING

AND COMMISSIONING OF 15kV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL

POWER PLANT

Project Location: BATAG DIESEL POWER PLANT, BRGY.

MARUBAY, LAOANG, NORTHERN SAMAR

PR No. : **S2-BTG22-009** 

Contents

SECTION I - INVITATION TO BID

SECTION II - INSTRUCTIONS TO BIDDERS

SECTION III - BID DATA SHEET

SECTION IV - GENERAL CONDITIONS OF CONTRACT

SECTION V - SPECIAL CONDITIONS OF CONTRACT

SECTION VI - TECHNICAL SPECIFICATIONS

SECTION VII - BID PRICE SCHEDULE

SECTION VIII - BIDDING FORMS

SECTION IX - BID DRAWINGS

**Design and Development Department** 



# **SECTION I**

# **INVITATION TO BID**





# National Power Corporation INVITATION TO BID PUBLIC BIDDING -- BCS 2022-0472

The NATIONAL POWER CORPORATION (NPC), through its approved Corporate Budget
of CY 2022 intends to apply the sum of (Please see schedule below) being the Approved Budget
for the Contract (ABC) to payments under the contract. Bids received in excess of the ABC shall be
automatically rejected at Bid opening.

PR Nos./PB Ref No. & Description	Similar Contracts	Pre-bid Conference	Bid Submission / Opening	ABC/ Amt. of Bid Docs
S3-KDP22-011 / PB220711-JC00246 (PB2) Supply and Delivery of Crankshaft Intended for 540kW Perkins with Engine No. 2806C-E18TAG3 of Kalamansig DPP	Supply and Delivery of Diesel Generating Sets or Mechanical and/or Electrical Parts / Components / Equipment for Diesel Generating Sets	25 July 2022 9:30 A.M	08 August 2022 9:30 A.M	₽ 1,215,000.00 / ₽ 5,000.00
S2-VMT22-005 / PB220808-JD00294 Supply, Delivery and Test of 15kV Insulation Resistance Tester for Visayas Maintenance & Technical Services Division	Supply, delivery and test of insulation resistance tester or electrical testing equipment / instruments	25 July 2022 9:30 A.M	08 August 2022 9:30 A.M	₽ 3,500,000.00 / ₽ 5,000.00
HO-PIB22-010 / PB220808-HG00295  Supply, Delivery, Installation, Test and Commissioning of 1 x 100kW Modular Diesel Generating Set and Associated Electrical Equipment for Mababangbaybay DPP, Claveria Burias Island, Masbate	Supply, Delivery, Installation, Test and Commissioning or Construction of Power Facilities, Installation, Test and Commissioning of Diesel Generating Set/s with at least one-unit capacity of 100 kW Prime or Continuous Power with power transformer/s of at least 150 kVA rating	25 July 2022 9:30 A.M	09 August 2022 9:30 A.M	₽ 7,065,000.00 / ₽ 10,000.00

2. The NPC now invites bids for Items listed above. Delivery of the Goods is required (see table below) specified in the Technical Specifications. Bidders should have completed, within (see table below) from the date of submission and receipt of bids, a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. (Instruction to Bidders).

PR No/s. / PB Ref No/s.	Delivery Period / Contract Duration	Relevant Period of SLCC reckoned from the date of submission & receipt of bids
S3-KDP22-011	Ninety (90) Calendar Days	Ten (10) Years
S2-VMT22-005	Sixty (60) Calendar Days	Five (5) Years
HO-PIB22-010	Two Hundred Forty (240) Calendar Days	Fifteen (15) Years
S2-BTG22-009	Ninety (90) Calendar Days	Ten (10) Years

3. Bidding will be conducted through open competitive bidding procedures using a non-discretionary "pass/fail" criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.

Bidding is restricted to Filipino citizens/sole proprietorships, partnerships, or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines, and to citizens or organizations of a country the laws or regulations of which grant similar rights or privileges to Filipino citizens, pursuant to RA 5183.

- Prospective Bidders may obtain further information from National Power Corporation, Bids and Contracts Services Division and inspect the Bidding Documents at the address given below during office hours (8:00AM to 5:00PM), Monday to Friday.
- A complete set of Bidding Documents may be acquired by interested Bidders from the given address and website(s) and upon payment of the applicable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB. <u>Bidding fee may be refunded in accordance with the guidelines based on the grounds provided under Section 41 of R.A. 9184 and its Revised IRR.</u>
- 6. The National Power Corporation will hold Pre-Bid Conference (see table above) and/or through video conferencing or webcasting which shall be open to prospective bidders.

Only registered bidder/s shall be allowed to participate for the conduct of virtual pre-bid conference. **Unregistered bidders** may attend the Pre-Bid Conference at the Kañao Room, NPC subject to the following:

a. Only a maximum of two (2) representatives from each bidder / company shall be allowed to participate during the virtual pre-bid conference.

b. A "No Face mask / No Entry" policy shall be implemented in the NPC premises. Face mask shall be 3-ply surgical or KN95 mask type.

c. The requirements herein stated including the medium of submission shall be subject to GPPB Resolution No. 09-2020 dated 07 May 2020

- d. The Guidelines on the Implementation of Early Procurement Activities (EPA) shall be subject to GPPB Circular No. 06-2019 dated 17 July 2019
- 7. Bids must be duly received by the BAC Secretariat through (i) manual submission at the office address indicated below; (ii) online or electronic submission before the specified time stated in the table above for opening of bids. Late bids shall not be accepted.
- 8. All Bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated
- 9. Bid opening shall be on Kañao Function Room, NPC Head Office, Diliman, Quezon City and/or via online platform to be announced by NPC. Bids will be opened in the presence of the bidders' representatives who choose to attend the activity.
- 10. The National Power Corporation reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised IRR of R.A. No. 9184, without thereby incurring any liability to the affected bidder or
- 11. For further information, please refer to:

# Bids and Contracts Services Division, **Logistics Department**

BIR Road cor. Quezon Avenue

Diliman, Quezon City

Tel Nos.: 8924-5211 and 8921-3541 local 5504/5611/5361

Fax No.: 8922-1622

Email: bcsd@napocor.gov.ph / bcsd\_napocor@yahoo.com

12. You may visit the following websites:

For downloading of Bidding Documents: https://www.napocor.gov.ph/bcsd/bids.php

RENE B. BARRUELA

Vice President, Corporate Affairs Group and Chairman, Bids and Awards Committee

PR NO. \$2-BTG22-009

# **SECTION II**

# INSTRUCTIONS TO BIDDERS

# **SECTION II – INSTRUCTIONS TO BIDDERS**

# **TABLE OF CONTENTS**

Claus	se No.	Page no.
1.	SCOPE OF BID	
2.	FUNDING INFORMATION	1
3.	BIDDING REQUIREMENTS	1
4.	CORRUPT, FRAUDULENT, COLLUSIVE, AND COERCIVE PRACTICES	1
5.	ELIGIBLE BIDDERS	1
6.	ORIGIN OF GOODS	2
7.	SUBCONTRACTS	2
8.	PRE-BID CONFERENCE	2
9.	CLARIFICATION AND AMENDMENT OF BIDDING DOCUMENTS	3
10.	DOCUMENTS COMPRISING THE BID: ELIGIBILITY AND TECHNICAL COMPONENTS	3
11.	DOCUMENTS COMPRISING THE BID: FINANCIAL COMPONENT	3
12.	BID PRICES	3
13.	BID AND PAYMENT CURRENCIES	4
14.	BID SECURITY	4
15.	SEALING AND MARKING OF BIDS	, Z
16.	DEADLINE FOR SUBMISSION OF BIDS	<del>5</del>
17.	OPENING AND PRELIMINARY EXAMINATION OF BIDS	<i>ξ</i>
18.	DOMESTIC PREFERENCE	5
19.	DETAILED EVALUATION AND COMPARISON OF BIDS	E
20.	Post-Qualification	<del>6</del>
21.	SIGNING OF THE CONTRACT	6

# SECTION II - INSTRUCTIONS TO BIDDERS

# 1. Scope of Bid

The National Power Corporation (NPC or NAPOCOR) wishes to receive Bids for the SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15KV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT, with identification number PR No S2-BTG22-009.

The Procurement Project (referred to herein as "Project") is composed of one (1) lot and will be awarded to one (1) Bidder in one complete contract, the details of which are described in Section VI (Technical Specifications).

# 2. Funding Information

- 2.1. The GOP through the source of funding as indicated below for CY 2022 in the amount of ₽ 1,675,000.00.
- 2.2. The source of funding is the Corporate Operating Budget of the National Power Corporation.

# 3. Bidding Requirements

The Bidding for the Project shall be governed by all the provisions of RA No. 9184 and its 2016 revised IRR, including its Generic Procurement Manuals and associated policies, rules and regulations as the primary source thereof, while the herein clauses shall serve as the secondary source thereof.

Any amendments made to the IRR and other GPPB issuances shall be applicable only to the ongoing posting, advertisement, or **IB** by the BAC through the issuance of a supplemental or bid bulletin.

The Bidder, by the act of submitting its Bid, shall be deemed to have verified and accepted the general requirements of this Project, including other factors that may affect the cost, duration and execution or implementation of the contract, project, or work and examine all instructions, forms, terms, and project requirements in the Bidding Documents.

# 4. Corrupt, Fraudulent, Collusive, and Coercive Practices

The Procuring Entity, as well as the Bidders and Suppliers, shall observe the highest standard of ethics during the procurement and execution of the contract. They or through an agent shall not engage in corrupt, fraudulent, collusive, coercive, and obstructive practices defined under Annex "I" of the 2016 revised IRR of RA No. 9184 or other integrity violations in competing for the Project.

# 5. Eligible Bidders

5.1. Only Bids of Bidders found to be legally, technically, and financially capable will be evaluated.



5.2. Foreign ownership exceeding those allowed under the rules may participate when citizens, corporations, or associations of a country, included in the list issued by the GPPB, the laws or regulations of which grant reciprocal rights or privileges to citizens, corporations, or associations of the Philippines.

The foreign bidder claiming eligibility by reason of their country's extension of reciprocal rights to Filipinos shall submit a certification from the relevant government office of their country stating that Filipinos are allowed to participate in their government procurement activities for the same item/product. The said certification shall be validated during the post-qualification of bidders.

- 5.3. Pursuant to Section 23.4.1.3 of the 2016 revised IRR of RA No.9184, the Bidder shall have an SLCC that is at least one (1) contract similar to the Project the value of which, adjusted to current prices using the PSA's CPI, must be at least equivalent to at least fifty percent (50%) of the ABC.
- 5.4. The Bidders shall comply with the eligibility criteria under Section 23.4.1 of the 2016 IRR of RA No. 9184.

# 6. Origin of Goods

There is no restriction on the origin of goods other than those prohibited by a decision of the UN Security Council taken under Chapter VII of the Charter of the UN, subject to Domestic Preference requirements under ITB Clause 18.

## 7. Subcontracts

7.1. The Bidder may subcontract portions of the Project to the extent allowed by the Procuring Entity as stated herein, but in no case more than twenty percent (20%) of the Project.

The portions of Project and the maximum percentage allowed to be subcontracted are indicated in the BDS, which shall not exceed twenty percent (20%) of the contracted Goods.

- 7.2. The Supplier may identify its subcontractor during the contract implementation stage. Subcontractors identified during the bidding may be changed during the implementation of this Contract. Subcontractors must submit the documentary requirements under Section 23.1 of the 2016 revised IRR of RA No. 9184 and comply with the eligibility criteria specified in ITB Clause 5 to the implementing or end-user unit.
- 7.3. Subcontracting of any portion of the Project does not relieve the Supplier of any liability or obligation under the Contract. The Supplier will be responsible for the acts, defaults, and negligence of any subcontractor, its agents, servants, or workmen as fully as if these were the Supplier's own acts, defaults, or negligence, or those of its agents, servants, or workmen.

## 8. Pre-Bid Conference

The Procuring Entity will hold a pre-bid conference for this Project on the specified date and time and either at its physical address and/or through videoconferencing/webcasting as indicated in paragraph 6 of the **IB**.



9.

Clarification and Amendment of Bidding Documents

Prospective bidders may request for clarification on and/or interpretation of any part of the Bidding Documents. Such requests must be in writing and received by the Procuring Entity, either at its given address or through electronic mail indicated in the **IB**, at least ten (10) calendar days before the deadline set for the submission and receipt of Bids.

# 10. Documents comprising the Bid: Eligibility and Technical Components

- 10.1. The first envelope shall contain the eligibility and technical documents of the Bid as specified in Section VIII (NPCSF-GOODS-01 Checklist of Technical and Financial Documents).
- 10.2. The Bidder's SLCC as indicated in ITB Clause 5.3 should have been completed within Ten (10) Years prior to the deadline for the submission and receipt of bids.
- 10.3. If the eligibility requirements or statements, the bids, and all other documents for submission to the BAC are in foreign language other than English, it must be accompanied by a translation in English, which shall be authenticated by the appropriate Philippine foreign service establishment, post, or the equivalent office having jurisdiction over the foreign bidder's affairs in the Philippines. Similar to the required authentication above, for Contracting Parties to the Apostille Convention, only the translated documents shall be authenticated through an apostille pursuant to GPPB Resolution No. 13-2019 dated 23 May 2019. The English translation shall govern, for purposes of interpretation of the bid.
- 10.4. The Statement of the bidder's Single Largest Completed Contract (SLCC) (NPCSF-GOODS-03) and List of all Ongoing Government & Private Contracts Including Contracts Awarded but not yet Started (NPCSF-GOODS-02) shall comply with the documentary requirements specified in the <u>BDS.</u>

# 11. Documents comprising the Bid: Financial Component

- 11.1. The second bid envelope shall contain the financial documents for the Bid as specified in Section VIII (NPCSF-GOODS-01 - Checklist of Technical and Financial Documents).
- 11.2. If the Bidder claims preference as a Domestic Bidder or Domestic Entity, a certification issued by DTI shall be provided by the Bidder in accordance with Section 43.1.3 of the 2016 revised IRR of RA No. 9184.
- 11.3. Any bid exceeding the ABC indicated in paragraph 1 of the **IB** shall not be accepted.
- 11.4. For Foreign-funded Procurement, a ceiling may be applied to bid prices provided the conditions are met under Section 31.2 of the 2016 revised IRR of RA No. 9184.

# 12. Bid Prices

- 12.1. Prices indicated on the Price Schedule shall be entered separately in the following manner:
  - a. For Goods offered from within the Procuring Entity's country:



- i. The price of the Goods quoted EXW (ex-works, ex-factory, exwarehouse, ex-showroom, or off-the-shelf, as applicable);
- The cost of all customs duties and sales and other taxes already paid or payable;
- iii. The cost of transportation, insurance, and other costs incidental to delivery of the Goods to their final destination; and
- iv. The price of other (incidental) services, if any, listed in the BDS.

## b. For Goods offered from abroad:

- i. Unless otherwise stated in the BDS, the price of the Goods shall be quoted delivered duty paid (DDP) with the place of destination in the Philippines as specified in the BDS. In quoting the price, the Bidder shall be free to use transportation through carriers registered in any eligible country. Similarly, the Bidder may obtain insurance services from any eligible source country.
- ii. The price of other (incidental) services, if any, as listed in the BDS.

# 13. Bid and Payment Currencies

- 13.1. For Goods that the Bidder will supply from outside the Philippines, the bid prices may be quoted in the local currency or tradeable currency accepted by the BSP at the discretion of the Bidder. However, for purposes of bid evaluation, Bids denominated in foreign currencies, shall be converted to Philippine currency based on the exchange rate as published in the BSP reference rate bulletin on the day of the bid opening.
- 13.2. Payment of the contract price shall be made in Philippine Pesos.

# 14. Bid Security

- 14.1. The Bidder shall submit a Bid Securing Declaration or any form of Bid Security in the amount indicated in the BDS, which shall be not less than the percentage of the ABC in accordance with the schedule in the BDS.
- 14.2. The Bid and bid security shall be valid for One Hundred Twenty (120) calendar days from the date of opening of bids. Any Bid not accompanied by an acceptable bid security shall be rejected by the Procuring Entity as non-responsive.

# 15. Sealing and Marking of Bids

Each Bidder shall submit one copy of the first and second components of its Bid.

The Procuring Entity may request additional hard copies and/or electronic copies of the Bid. However, failure of the Bidders to comply with the said request shall not be a ground for disqualification.

If the Procuring Entity allows the submission of bids through online submission or any other electronic means, the Bidder shall submit an electronic copy of its Bid, which must



be digitally signed. An electronic copy that cannot be opened or is corrupted shall be considered non-responsive and, thus, automatically disqualified.

## 16. Deadline for Submission of Bids

16.1. The Bidders shall submit on the specified date and time and either at its physical address or through online submission as indicated in paragraph 7 of the IB.

# 17. Opening and Preliminary Examination of Bids

17.1. The BAC shall open the Bids in public at the time, on the date, and at the place specified in paragraph 9 of the IB. The Bidders' representatives who are present shall sign a register evidencing their attendance. In case videoconferencing, webcasting or other similar technologies will be used, attendance of participants shall likewise be recorded by the BAC Secretariat.

In case the Bids cannot be opened as scheduled due to justifiable reasons, the rescheduling requirements under Section 29 of the 2016 revised IRR of RA No. 9184 shall prevail.

17.2. The preliminary examination of bids shall be governed by Section 30 of the 2016 revised IRR of RA No. 9184.

# 18. Domestic Preference

18.1. The Procuring Entity will grant a margin of preference for the purpose of comparison of Bids in accordance with Section 43.1.2 of the 2016 revised IRR of RA No. 9184.

# 19. Detailed Evaluation and Comparison of Bids

- 19.1. The Procuring Entity's BAC shall immediately conduct a detailed evaluation of all Bids rated "passed," using non-discretionary pass/fail criteria. The BAC shall consider the conditions in the evaluation of Bids under Section 32.2 of the 2016 revised IRR of RA No. 9184.
- 19.2. If the Project allows partial bids, bidders may submit a proposal on any of the lots or items, and evaluation will be undertaken on a per lot or item basis, as the case maybe. In this case, the Bid Security as required by ITB Clause 14 shall be submitted for each lot or item separately.
- 19.3. The descriptions of the lots or items shall be indicated in Section VI (Technical Specifications), although the ABCs of these lots or items are indicated in the BDS for purposes of the NFCC computation pursuant to Section 23.4.2.6 of the 2016 revised IRR of RA No. 9184. The NFCC must be sufficient for the total of the ABCs for all the lots or items participated in by the prospective Bidder.
- 19.4. The Project shall be awarded to one (1) Bidder in one complete contract.
- 19.5. Except for bidders submitting a committed Line of Credit from a Universal or Commercial Bank in lieu of its NFCC computation, all Bids must include the NFCC computation pursuant to Section 23.4.1.4 of the 2016 revised IRR of RA No. 9184, which must be sufficient for the total of the ABCs for all the lots or



items participated in by the prospective Bidder. For bidders submitting the committed Line of Credit, it must be at least equal to ten percent (10%) of the ABCs for all the lots or items participated in by the prospective Bidder.

# 20. Post-Qualification

20.1. Within a non-extendible period of five (5) calendar days from receipt by the Bidder of the notice from the BAC that it submitted the Lowest Calculated Bid, the Bidder shall submit its latest income and business tax returns filed and paid through the BIR Electronic Filing and Payment System (eFPS) and other appropriate licenses and permits required by law and stated in the BDS.

# 21. Signing of the Contract

21.1. The documents required in Section 37.2 of the 2016 revised IRR of RA No. 9184 shall form part of the Contract. Additional Contract documents are indicated in the BDS.



# **SECTION III**

# **BID DATA SHEET**

# **SECTION III - BID DATA SHEET**

ITB Clause	
5.3	For this purpose, similar contracts shall refer to supply, delivery, installation, testing and commissioning of Automatic Circuit Recloser (at least 15kV) or substation equipment.
	The Single Largest Completed Contract (SLCC) as declared by the bidder shall be verified and validated to ascertain such completed contract. Hence, bidders must ensure access to sites of such projects/equipment to NPC representatives for verification and validation purposes during post-qualification process.
	It shall be a ground for disqualification, if verification and validation cannot be conducted for reasons attributable to the Bidder.
7.1	Subcontracting may be allowed on transport, local/non-skilled labor under the supervision of the Bidder. The Bidder shall not be relieved from any liability or obligation that may arise from the performance of the Subcontractor.
10.4	The list of on-going contracts (Form No. NPCSF-GOODS-02) shall be supported by the following documents for each on-going contract to be submitted during Post-Qualification:
	Contract/Purchase Order and/or Notice of Award
	Certification coming from the project owner/client that the performance is satisfactory as of the bidding date
	The bidder shall declare in this form all his on-going government and private contracts including contracts where the bidder (either as individual or as a Joint Venture) is a partner in a Joint Venture agreement other than his current joint venture where he is a partner. Non declaration will be a ground for disqualification of bid.
	The Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid (Form No. NPCSF-GOODS-03) shall be supported by the following documents to be submitted during <b>Bid Opening:</b>
	Contract/Purchase Order
	<ol> <li>Certificate of Acceptance; or Certificate of Completion; or Official Receipt (O.R); or Sales Invoice</li> </ol>
	The prospective bidders shall declare its Joint Venture partner during the purchase of bid/tender documents. Any single bidder/s who already procured/secured the bidding documents but want to avail the Joint Venture Agreement (JVA) shall inform the BAC in writing prior to the bid opening for records and documentation purposes. Failure to do so shall be a ground for disqualification/non-acceptance of its bid.



10.5	Bidders shall also submit the following requirements in their first envelope Eligibility and Technical Component of their bid:		
	Data and Information to be submitted with the Bid/Proposal as specified in Clause TS-11.0(a) of Section VI - Technical Specifications;		
	Complete eligibility documents of the proposed sub-contractor, if any		
12	The price of the Goods shall be quoted DDP Project Site or the applicable International Commercial Terms (INCOTERMS) for this Project.		
14.1	The bid security shall be in the form of a Bid Securing Declaration, or any of the following forms and amounts:		
	<ul> <li>a) The amount of not less two percent (2%) of ABC, if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit; or</li> </ul>		
	b) The amount of not less than five percent (5%) of ABC, if bid security is in Surety Bond.		
19.3	The Goods are grouped together in one (1) lot and will be awarded to one (1) Bidder in one complete contract.		
	Partial bid is not allowed. The Goods are grouped in a single lot and the lot shall not be divided into sub-lots for the purpose of bidding, evaluation, and contract award.		
	The Bidders bid offer must be within the ABC of the lot.		
	Bid offers that exceed the ABC of the lot or with incomplete price, shall be rejected.		
19.5	If the Bidder opted to submit a Committed Line of Credit (CLC), the bidder must submit a granted credit line valid/effective at the date of bidding.		
20.1	Additional documents to be submitted during Post-Qualification:		
	<ul> <li>a. Contract/Purchase Order and/or Notice of Award for the contracts stated in the List of all Ongoing Government &amp; Private Contracts Including Contracts Awarded but not yet Started (NPCSF-GOODS-02);</li> </ul>		
	<ul> <li>b. Certification coming from the project owner/client that the performance is satisfactory as of the bidding date for all ongoing contracts stated in Form NPCSF-GOODS-02;</li> </ul>		
	c. Documents to be submitted during post-qualification process as specified in Clause TS-11.0(b) of Section VI-Technical Specifications		
	Manufacturer's brochures, manuals and other supporting documents of equipment, materials, hardware and tools proposed by the bidders must comply with the technical specifications of such equipment, materials, hardware and tools. It shall be a ground for disqualification if the submitted brochures, manuals and other supporting documents are determined not		



	complying with the specifications during technical evaluation and post- qualification process.
	Equipment, materials, hardware and tools proposed by the winning bidder to be supplied, which were evaluated to be complying with the technical specifications, shall not be replaced and must be the same items to be delivered/installed/used during the contract implementation. Any proposed changes/replacement of said items may be allowed on meritorious reasons subject to validation and prior approval by NPC.
20.2	The licenses and permits relevant to the Project and the corresponding law requiring it as specified in the Technical Specifications, if any.
21.2	Notice to Proceed.



# **SECTION IV**

# GENERAL CONDITIONS OF CONTRACT

# **SECTION IV – GENERAL CONDITIONS OF CONTRACT**

# **TABLE OF CONTENTS**

Clause No. Title		Page no.
1.	SCOPE OF CONTRACT	1
2.	ADVANCE PAYMENT AND TERMS OF PAYMENT	1
3.	PERFORMANCE SECURITY	1
4.	INSPECTION AND TESTS	
5.	WARRANTY	2
6.	LIABILITY OF THE SUPPLIER	2



# SECTION IV – GENERAL CONDITIONS OF CONTRACT

# 1. Scope of Contract

This Contract shall include all such items, although not specifically mentioned, that can be reasonably inferred as being required for its completion as if such items were expressly mentioned herein. All the provisions of RA No. 9184 and its 2016 revised IRR, including the Generic Procurement Manual, and associated issuances, constitute the primary source for the terms and conditions of the Contract, and thus, applicable in contract implementation. Herein clauses shall serve as the secondary source for the terms and conditions of the Contract.

This is without prejudice to Sections 74.1 and 74.2 of the 2016 revised IRR of RA No. 9184 allowing the GPPB to amend the IRR, which shall be applied to all procurement activities, the advertisement, posting, or invitation of which were issued after the effectivity of the said amendment.

Additional requirements for the completion of this Contract shall be provided in the Special Conditions of Contract (SCC).

# 2. Advance Payment and Terms of Payment

- 2.1. Advance payment of the contract amount is provided under Annex "D" of the revised 2016 IRR of RA No. 9184.
- 2.2. The Procuring Entity is allowed to determine the terms of payment on the partial or staggered delivery of the Goods procured, provided such partial payment shall correspond to the value of the goods delivered and accepted in accordance with prevailing accounting and auditing rules and regulations. The terms of payment are indicated in the **SCC**.

# 3. Performance Security

- 3.1. Within ten (10) calendar days from receipt of the Notice of Award by the Bidder from the Procuring Entity but in no case later than the signing of the Contract by both parties, the successful Bidder shall furnish the performance security in any of the forms prescribed in Section 39 of the 2016 revised IRR of RA No. 9184.
- 3.2. The performance bond to be posted by the Contractor must also comply with additional requirements specified in the SCC.

# 4. Inspection and Tests

The Procuring Entity or its representative shall have the right to inspect and/or to test the Goods to confirm their conformity to the Project specifications at no extra cost to the Procuring Entity in accordance with the Generic Procurement Manual. In addition to tests in the SCC, Section VI (Technical Specifications) shall specify what inspections and/or tests the Procuring Entity requires, and where they are to be



conducted. The Procuring Entity shall notify the Supplier in writing, in a timely manner, of the identity of any representatives retained for these purposes.

All reasonable facilities and assistance for the inspection and testing of Goods, including access to drawings and production data, shall be provided by the Supplier to the authorized inspectors at no charge to the Procuring Entity.

# 5. Warranty

- 5.1 In order to assure that manufacturing defects shall be corrected by the Supplier, a warranty shall be required from the Supplier as provided under Section 62.1 of the 2016 revised IRR of RA No. 9184.
- 5.2 The Procuring Entity shall promptly notify the Supplier in writing of any claims arising under this warranty. Upon receipt of such notice, the Supplier shall, repair or replace the defective Goods or parts thereof without cost to the Procuring Entity, pursuant to the Generic Procurement Manual.

# 6. Liability of the Supplier

The Supplier's liability under this Contract shall be as provided by the laws of the Republic of the Philippines.

If the Supplier is a joint venture, all partners to the joint venture shall be jointly and severally liable to the Procuring Entity.



PR NO. S2-BTG22-009

# **SECTION V**

# SPECIAL CONDITIONS OF CONTRACT



# **SECTION IV - SPECIAL CONDITIONS OF CONTRACT**

GCC Clause		
1	Delivery and Documents –	
	The delivery terms applicable to the Contract is DDP delivered to the projective site specified in the technical specifications, in accordance with INCOTERM Risk and title will pass from the Supplier to the Procuring Entity upon receased and final acceptance of the Goods at their final destination.	
	Delivery of the Goods shall be made by the Supplier in accordance with the terms specified in Section VI – Technical Specifications. The details of shipping and/or other documents to be furnished by the Supplier are as follows:  For Goods supplied from within the Philippines	
	Jpon delivery of the Goods to the Project Site, the Supplier shall notify the Procuring Entity and present the following documents to the Procuring Entity:	Э
	<ul> <li>Original and four copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount;</li> </ul>	;*
	ii) Original and four copies of Supplier's factory test/inspection report;	
	iii) Original and four copies of the certificate of origin (for imported Goods);	
	<ul> <li>Delivery receipt detailing number and description of items received signed by the Procuring Entity's representative at the Project Site;</li> </ul>	Ė
	<ul> <li>Certificate of Completion/Inspection Report signed by the Procuring Entity's representative at the Project Site;</li> </ul>	)
	vi) Original and four copies of the Inspection Receiving Report signed by the Procuring Entity's representative at the Project Site;	)
	vii) Original and four copies of the Manufacturer's and/or Supplier's warranty certificate; and	1
	viii) Documents specified in the Technical Specifications, if any.	
;	For Goods supplied from abroad:	
	Upon shipment, the Supplier shall notify the Procuring Entity and the insurance company by e-mail the full details of the shipment, including Contract Number, lescription of the Goods, quantity, vessel, bill of lading number and date, port of loading, date of shipment, port of discharge etc. Upon delivery to the Project Site, the Supplier shall notify the Procuring Entity and present the following locuments as applicable with the documentary requirements of any letter of credit issued taking precedence:	., t



- (i) Original and four copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount:
- (ii) Original and four copies of the negotiable, clean shipped on board bill of lading marked "freight pre-paid" and five copies of the non-negotiable bill of lading;
- (iii) Original and four copies of Supplier's factory test/inspection report;
- (iv) Delivery receipt detailing number and description of items received signed by the Procuring Entity's representative at the Project Site:
- (v) Certificate of Completion/Inspection Report signed by the Procuring Entity's representative at the Project Site;
- (vi) Original and four copies of the Inspection Receiving Report signed by the Procuring Entity's representative at the Project Site;
- (vii) Original and four copies of the certificate of origin (for imported Goods);and
- (viii) Original and four copies of the Manufacturer's and/or Supplier's warranty certificate including all other documents specified in the Technical Specifications, if any.

For purposes of this Clause the Procuring Entity's Representative at the Project Site is Vice President - SPUG.

#### Incidental Services -

The Supplier is required to provide all of the following services, including additional services, if any, specified in Section VI. Schedule of Requirements:

- performance or supervision of on-site assembly and/or start-up of the supplied Goods;
- furnishing of tools required for assembly and/or maintenance of the supplied Goods;
- c. furnishing of a detailed operations and maintenance manual for each appropriate unit of the supplied Goods;
- d. performance or supervision or maintenance and/or repair of the supplied Goods, for a period of time agreed by the parties, provided that this service shall not relieve the Supplier of any warranty obligations under this Contract; and
- e. training of the Procuring Entity's personnel, at the Supplier's plant and/or on-site, in assembly, start-up, operation, maintenance, and/or repair of the supplied Goods.



 f. Additional requirements specified in Section VI – Technical Specifications, if any.

The Contract price for the Goods shall include the prices charged by the Supplier for incidental services and shall not exceed the prevailing rates charged to other parties by the Supplier for similar services.

#### Spare Parts -

The Supplier is required to provide all of the following materials, notifications, and information pertaining to spare parts manufactured or distributed by the Supplier:

- such spare parts as the Procuring Entity may elect to purchase from the Supplier, provided that this election shall not relieve the Supplier of any warranty obligations under this Contract; and
- 2. in the event of termination of production of the spare parts:
  - i. advance notification to the Procuring Entity of the pending termination, in sufficient time to permit the Procuring Entity to procure needed requirements; and
  - ii. following such termination, furnishing at no cost to the Procuring Entity, the blueprints, drawings, and specifications of the spare parts, if requested

The spare parts and other components required are listed in Section VI (Technical Specifications) and Section VII (Schedule of Requirements/Bid Price Schedule) and the costs thereof are included in the contract price.

The Supplier shall carry sufficient inventories to assure ex-stock supply of consumable spare parts or components for the Goods for the period specified in the Technical Specifications.

Spare parts or components shall be supplied as promptly as possible, but in any case, within three (3) months of placing the order.

## Packaging -

The Supplier shall provide such packaging of the Goods as is required to prevent their damage or deterioration during transit to their final destination, as indicated in this Contract. The packaging shall be sufficient to withstand, without limitation, rough handling during transit and exposure to extreme temperatures, salt and precipitation during transit, and open storage. Packaging case size and weights shall take into consideration, where appropriate, the remoteness of the Goods' final destination and the absence of heavy handling facilities at all points in transit.

The packaging, marking, and documentation within and outside the packages shall comply strictly with such special requirements as shall be expressly provided for in the Contract, including additional requirements, if any, specified below, and in any subsequent instructions ordered by the Procuring Entity.



The outer packaging must be clearly marked on at least four (4) sides as follows:

Name of the Procuring Entity
Name of the Supplier
Contract Description
Final Destination
Gross weight
Any special lifting instructions
Any special handling instructions
Any relevant HAZCHEM classifications

A packaging list identifying the contents and quantities of the package is to be placed on an accessible point of the outer packaging if practical. If not practical the packaging list is to be placed inside the outer packaging but outside the secondary packaging.

# Transportation -

Where the Supplier is required under Contract to deliver the Goods CIF, CIP, or DDP, transport of the Goods to the port of destination or such other named place of destination in the Philippines, as shall be specified in this Contract, shall be arranged and paid for by the Supplier, and the cost thereof shall be included in the Contract Price.

Where the Supplier is required under this Contract to transport the Goods to a specified place of destination within the Philippines, defined as the Project Site, transport to such place of destination in the Philippines, including insurance and storage, as shall be specified in this Contract, shall be arranged by the Supplier, and related costs shall be included in the contract price.

Where the Supplier is required under Contract to deliver the Goods CIF, CIP or DDP, Goods are to be transported on carriers of Philippine registry. In the event that no carrier of Philippine registry is available, Goods may be shipped by a carrier which is not of Philippine registry provided that the Supplier obtains and presents to the Procuring Entity certification to this effect from the nearest Philippine consulate to the port of dispatch. In the event that carriers of Philippine registry are available but their schedule delays the Supplier in its performance of this Contract the period from when the Goods were first ready for shipment and the actual date of shipment the period of delay will be considered force majeure.

The Procuring Entity accepts no liability for the damage of Goods during transit other than those prescribed by INCOTERMS for DDP deliveries. In the case of Goods supplied from within the Philippines or supplied by domestic Suppliers risk and title will not be deemed to have passed to the Procuring Entity until their receipt and final acceptance at the final destination.

# Intellectual Property Rights -

The Supplier shall indemnify the Procuring Entity against all third-party claims of infringement of patent, trademark, or industrial design rights arising from use of the Goods or any part thereof.



2.2

PR NO. S2-BTG22-009

Advance payment not to exceed fifteen percent (15%) of the contract amount shall be allowed and paid within sixty (60) calendar days from effectivity of the contract and upon the submission to and acceptance by the Procuring Entity of an irrevocable letter of credit or bank guarantee issued by a Universal or Commercial Bank. The irrevocable letter of credit or bank guarantee must be for an equivalent amount, shall remain valid until the goods are delivered, and accompanied by a claim for advance payment.

All progress payments shall first be charged against the advance payment until the latter has been fully exhausted.

The terms of payment shall be as follows:

# 1) For Supply and Delivery Contracts:

- (a) On Contract Effectivity: Advance payment of Fifteen percent (15%) of the total Contract Price shall be paid within sixty (60) days from effectivity of the Contract and upon submission of a claim and an irrevocable letter of credit or bank guarantee issued by a Universal or Commercial Bank for the equivalent amount valid until the Goods are delivered and in the form provided in Section VIII- Bidding Forms.
- (b) On Delivery: Eighty percent (80%) of the Contract Price of the delivered Goods shall be considered for payment, less the total amount of advance payment, if any and other deductions. If the amount is sufficient to fully recoup the advance payment, the remainder after deductions shall be paid to the Supplier within sixty (60) days after the date of receipt of the Goods and upon submission of the documents (i) through (vi) specified in the SCC provision on Delivery and Documents. Otherwise, the total delivery payment shall be charged against the advance payment and the remaining advance payment will be fully recouped from the succeeding claims.
- (c) On Acceptance: The remaining twenty percent (20%) of the Contract Price of the *delivered Goods* shall be paid to the Supplier within sixty (60) days after the date of submission of the acceptance and inspection certificate for the respective delivery issued by the Procuring Entity's authorized representative. In the event that no acceptance certificate is issued by the Procuring Entity's authorized representative within forty five (45) days after successful test and commissioning, if required, the Supplier shall have the right to claim payment of the remaining twenty percent (20%) subject to the Procuring Entity's own verification of the reason(s) for the failure to issue documents (vii) and (viii) as described in the <u>SCC</u> provision on Delivery and Documents.

# 2) For Supply, Delivery, Installation, Test and Commissioning Contracts:

(a) On Contract Effectivity: Advance payment of Fifteen percent (15%) of the total Contract Price shall be paid within sixty (60) days from effectivity of the Contract and upon submission of a claim and an irrevocable letter of credit or bank guarantee issued by a Universal or



Commercial Bank for the equivalent amount valid until the Goods are delivered and in the form provided in Section VIII- Bidding Forms.

- (b) On Delivery: Eighty percent (80%) of the price of the **delivered Goods**, excluding price for installation, test and commissioning shall be considered for payment, less the total amount of advance payment, if any and other deductions. If the amount is sufficient to fully recoup the advance payment, the remainder after deductions shall be paid to the Supplier within sixty (60) days after the date of receipt of the Goods and upon submission of the documents (i) through (vi) specified in the <u>SCC</u> provision on Delivery and Documents. Otherwise, the total delivery payment shall be charged against the advance payment and the remaining advance payment will be fully recouped from the succeeding claims.
- (c) On Acceptance: The remaining twenty percent (20%) of the price of the **delivered Goods** plus price for installation, test and commissioning shall be paid to the Supplier within sixty (60) days after the date of submission of the acceptance and inspection certificate for the respective delivery issued by the Procuring Entity's authorized representative. In the event that no acceptance certificate is issued by the Procuring Entity's authorized representative within forty five (45) days after successful test and commissioning, the Supplier shall have the right to claim payment subject to the Procuring Entity's own verification of the reason(s) for the failure to issue documents (vii) and (viii) as described in the <u>SCC</u> provision on Delivery and Documents.
- 3) For Supply, Delivery, Installation, Test and Commissioning Contracts where Installation, Test and Commissioning prices are included in the supply price:
  - (a) On Contract Effectivity: Advance payment of Fifteen percent (15%) of the total Contract Price shall be paid within sixty (60) days from effectivity of the Contract and upon submission of a claim and an irrevocable letter of credit or bank guarantee issued by a Universal or Commercial Bank for the equivalent amount valid until the Goods are delivered and in the form provided in Section VIII- Bidding Forms.
  - (b) On Delivery: Sixty percent (60%) of the price of the delivered Goods shall be considered for payment, less the total amount of advance payment, if any and other deductions. If the amount is sufficient to fully recoup the advance payment, the remainder after deductions shall be paid to the Supplier within sixty (60) days after the date of receipt of the Goods and upon submission of the documents (i) through (vi) specified in the SCC provision on Delivery and Documents. Otherwise, the total delivery payment shall be charged against the advance payment and the remaining advance payment will be fully recouped from the succeeding claims.
  - (c) On Acceptance: The remaining forty percent (40%) of the price of the delivered Goods shall be paid to the Supplier within sixty (60) days after the date of submission of the acceptance and inspection certificate for the respective delivery issued by the Procuring Entity's



	authorized representative. In the event that no acceptance certificate is issued by the Procuring Entity's authorized representative within forty five (45) days after successful test and commissioning, the Supplier shall have the right to claim payment subject to the Procuring Entity's own verification of the reason(s) for the failure to issue documents (vii) and (viii) as described in the SCC provision on Delivery and Documents
3.2	<ol> <li>The following must be indicated in the performance bond to be posted by the Contractor:</li> </ol>
	<ul> <li>i. Company Name</li> <li>ii. Correct amount of the Bond</li> <li>iii. Contract/Purchase Order Reference Number</li> <li>iv. Purpose of the Bond:     "To guarantee the faithful performance of the Principal's obligation to undertake (Contract/Purchase Order Description) in accordance with the terms and conditions of (Contract No. &amp; Schedule/Purchase Order No.) entered into by the parties."</li> </ul>
	<ol> <li>The bond shall remain valid and effective until the duration of the contract (should be specific date reckoned from the contract effectivity) plus sixty (60) days after NPC's acceptance of the last delivery/final acceptance of the project.</li> </ol>
	3. In case of surety bond, any extension of the contract duration or delivery period granted to the CONTRACTOR shall be considered as given, and any modification of the contract shall be considered as authorized, as if with the expressed consent of the surety, provided that such extension or modifications falls within the effective period of the said surety bond. However, in the event that the extension of the contract duration or delivery schedule would be beyond the effective period of the surety bond first posted, it shall be the sole obligation of the CONTRACTOR to post an acceptable Performance Security within ten (10) calendar days after the contract duration/delivery period extension has been granted by NPC.
	Other required conditions in addition to the standard policy terms issued by the Bonding Company:
	<ol> <li>The bond is a penal bond, callable on demand and the entire amount thereof shall be forfeited in favor of the Obligee upon default of the Principal without the need to prove or to show grounds or reasons for demand for the sum specified therein;</li> </ol>
	<li>The amount claimed by the Obligee under this bond shall be paid in full and shall never be subject to any adjustment by the Surety;</li>
	iii. In case of claim, the Surety shall pay such claim within sixty (60) days from receipt by the Surety of the Obligee's notice of claim/demand letter notwithstanding any objection thereto by the Principal.
4	The inspections and tests that will be conducted are specified in the Technical Specifications.



PR NO. S2-BTG22-009

SECTION VI - TECHNICAL SPECIFICATIONS

**SECTION VI** 

# TECHNICAL SPECIFICATIONS

# **PART I - TECHNICAL SPECIFICATIONS SECTION EW - ELECTRICAL WORKS**

# **TABLE OF CONTENTS**

	CLAUSE NO.	TITLE	PAGE NO.
	TS-1.0	GENERAL	1
	TS-2.0	SCOPE OF WORK	1
	TS-3.0	DELIVERY PERIOD AND LOCATION	,1
	TS-4.0	CODES AND STANDARD	2
	TS-5.0	WORKMANSHIP	2
	TS-6.0 TS-6.1 TS-6.2 TS-6.3 TS-6.4 TS-6.5 TS-6.6 TS-6.7 TS-6.8 TS-6.9 TS-6.10 TS-6.11 TS-6.12 TS-6.13 TS-6.14 TS-6.15 TS-6.15 TS-6.16	TECHNICAL REQUIREMENTS  General Interrupting Medium Insulation Medium Housing Materials Mounting. Control Cabinet Earthing Surge Arrester Bracket Marking and Nameplates Operating Mechanism Bushing Current Transformer Auxiliary Supply Control Design Features Sequence of Operation Protection Safety Features	333444455555
•	TS-6.18 TS-6.19	Metering Event Recorder/Histogram	8
	TS-7.0	SPARES	
	T <b>S-8.0</b> TS-8.1 TS-8.2 TS-8.3 TS-8.4	OTHER TECHNICAL REQUIREMENTS  Operating and Configuration Editor Software Program  Training Requirements  Test and Inspection  Packaging and Marking	8 9 9
	<b>TS-9.0</b> TS <b>-</b> 9.1	BUS CONDUCTOR AND LINE HARDWARE Technical Characteristics and Requirements	
	TS-10.0	ACCEPTANCE CRITERIA	11
•	TS-11.0	DRAWINGS AND DOCUMENTS TO BE SUBMITTED	12
	TS-12.0	GUARANTEE	13
	TS-13.0	MEASUREMENT OF PAYMENT	14

# Section VI – Technical Specifications

# PART I – TECHNICAL SPECIFICATIONS

#### TS-1.0 GENERAL

This specification covers the technical requirements for the Supply, Delivery, Installation, Testing and Commissioning of 15kV Automatic Circuit Recloser for Batag Diesel Power Plant.

All supplied instruments and accessories shall be new and unused. They shall be suitable for the intended purpose and shall comply with all applicable regulations, quality, and dimension standards.

The Supplier shall accept full responsibility for his work including documentation, preparation for shipment, inspection, warranty provisions and compliance with the applicable codes and standards and the requirements of this Specification.

#### TS-2.0 SCOPE OF WORK

The scope of works shall cover but not limited to the following:

- 1. Dismantling of existing 15kV Automatic Circuit Recloser; and
- Supply, Delivery, Installation, Test and Commissioning of the new 15kV Automatic Circuit Recloser and accessories/materials necessary for the interfacing with the existing system.

The following shall be included in the Supplier's scope of work:

- The Supplier shall be responsible for visiting the delivery site and take particular reference to its accessibility, means of transportation and all other factors that should be considered in carrying out the contract.
- 2. Provide equipment, tools, instruments and consumables necessary during equipment testing for satisfactory completion of the work; and
- 3. Submission of pertinent documents as per TS-10.0 Drawings and Documentation Requirements.

## TS-3.0 DELIVERY PERIOD AND LOCATION

The delivery period shall be *Ninety (90) Calendar Days* reckoned from receipt of Notice to Proceed.

The materials to be supplied shall be delivered to Batag Diesel Power Plant, Brgy. Marubay, Laoang, Northern Samar.



#### TS-4.0 CODES AND STANDARD

The equipment furnished shall be in accordance with, but not limited to, the latest issues of the following codes and standards, including all addenda, in effect at time of purchase order unless otherwise stated in this specification:

1.	American National Standards Institute	ANSI
2.	Institute of Electrical and Electronic Engineers	IEEE
3.	American Society for Testing and Materials	ASTM
4.	National Electrical Manufacturer's Association	NEMA
5.	Underwriters Laboratory	UL
6.	International Electro-Technical Commission	IEC
7.	International Standards Organization	ISO
8.	National Electrical Code	NEC
9.	National Electrical Safety Code	NESC
10.	Philippine Electrical Code	PEC
11.	Illuminating Engineering Society	IE\$
12.	Philippine National Standards	PNS

The latest edition of each standard shall mean the latest edition available at the date of contract signing.

In addition to the above codes and standards mentioned, the Supplier shall comply with all National and local laws, codes, regulations, statutes and ordinances.

Equipment or materials meeting other internationally accepted standards, which ensure an equal or higher quality than the standards mentioned, will also be accepted.

In the event of any apparent conflict among standards, codes or this specification, the Supplier shall refer the conflict to NPC for written resolution before start of fabrication. Final decision regarding the acceptance of proposed standards is the prerogative of NPC.

Standards listed in the equipment specification are used mainly for NPC's references. Other internationally known standards however, shall also apply, provided such standards are equivalent in all respect to the standard prescribed and to the specific requirements described in the individual equipment specification. The Supplier shall submit copies of such standards for NPC's review and approval.

#### TS-5.0 WORKMANSHIP

Workmanship shall be of first-class quality and in accordance with the best modern engineering practice for the manufacture, assembly, installation, testing and commissioning of equipment. All works shall be done by personnel skilled in the related professions and trades. All parts shall be made accurately to standard gauges so as to facilitate replacement and repairs. All special gauges and templates necessary for filed erection shall become the property of NPC.

The parts or components shall be designed and arranged so that they can be easily inspected, cleaned, erected, and dismantled without involving large



PR NO. S2-BTG22-009

scale dismantling. They shall be designed and manufactured in accordance with the latest recognized rules of workmanship and modern engineering practice.

The Supplier shall be responsible with all damages occurred during the dismantling and installation works. Existing equipment that will be damaged shall be replaced by the Supplier at no additional cost to NPC.

#### TS-6.0 TECHNICAL REQUIREMENTS

#### TS-6.1 General

The Automatic Circuit Recloser shall have rated characteristics as specified in the Technical Data Sheets (Part II of the Technical Specification).

The Automatic Circuit Recloser shall be mechanically and electrically trip free. Any applied close signal, either mechanically or electrically, shall not inhibit the recloser from tripping on the programmed time-current curve.

A manual operating handle shall be provided including an indicator flag for contact position indication.

Close and trip capacitors shall be used to store the necessary energy for operating the recloser. Only the close capacitor energy shall be used for closing while both capacitors are available for opening. Trip energy shall be available following any electrical close.

# TS-6.2 Interrupting Medium

The interrupting medium shall be vacuum type.

#### TS-6.3 Insulation Medium

Environmentally friendly cycloaliphatic epoxy or equivalent shall be used as dielectric medium. SF6 gas shall not be used.

# TS-6.4 Housing Materials

The tank shall be manufactured from a hot-dipped galvanized steel, 316 stainless or cast aluminum. Control cubicles shall be manufactured from 316 stainless steel. All support structures and associated bolts and nuts shall be hot dipped galvanized.

# TS-6.5 Mounting

The Automatic Circuit Recloser shall be suitable for single and double pole/H-frame mounting.

All recloser tanks are to be supplied with standard pole mounting brackets fixed to the rear of the tank. The bracket shall be designed to ensure that the recloser live parts have statutory clearances from the pole and the earthed metal equipment.



PR NO. S2-BTG22-009

The brackets and tank wall are to be of adequate strength to limit distortion, when mounted. Both the top and bottom bracket shall be suitable to carry the total weight of the tank.

A detailed drawing of the Auto-recloser mounting arrangement shall be submitted together with the proposal. The minimum phase-to-earth clearance including clearance to the structure shall be indicated on the drawing.

#### TS-6.6 Control Cabinet

The control cabinet shall be designed for the service condition specified, and fitted with substantial door securing devices.

The control shall be housed in a weatherproof steel cabinet (IP 65) with a padlockable internally hinged door and shall include a thermostatically controlled heater.

The control cabinet shall be mounted below the tank and shall be connected by a minimum of 20m long multi-core control cable. The multi-core cable shall be ultra violet stabilized and adequately screened against electrostatic and electromagnetic interference, which can cause malfunctioning of the protection or control equipment. This cable shall connect into both the recloser and the control cabinet by means of plug and socket arrangement.

# TS-6.7 Earthing

Earthing terminals shall be fitted to equipment. An earthing strap shall be provided between the lid and the tank.

# TS-6.8 Surge Arrester Bracket

Surge arrester bracket shall be provided for the arrester mounting which will serve as the connection point for the arrester earth. The brackets shall have an unpainted corrosion resistant metal connecting zone which has the capability to conduct surge arrester current.

## TS-6.9 Marking and Nameplates

Phase identification marking shall be provided on each bushing of the Auto circuit recloser.

A nameplate shall be provided using a non-ferrous material or stainless steel, with the following information:

- a. Manufacturer's Name
- b. Serial No.
- c. Rated Maximum Voltage
- d. Rated Continuous Current
- e. Rated Interrupting Current
- f. Rated Impulse Withstand Voltage



# TS-6.10 Operating Mechanism

A low voltage system supplied from a battery or voltage transformer may be used to operate a closing mechanism. Tripping energy shall be supplied from a spring mechanism automatically tensioned when the recloser is closed.

Internal batteries used to operate closing mechanism shall not dependent on recloser load current to maintain its state of charge.

The recloser shall incorporate provision to be manually operated using a standard operating stick in the event of failure in the electrical control system.

# TS-6.11 Bushing

The HV bushing shall be of high-quality glazed porcelain, or cycloaliphatic epoxy resin having a creepage length as specified in the Technical Data Sheet.

The Supplier shall provide bird guards for insulation protection between the load side and line side bushings.

#### TS-6.12 Current Transformer

A sensing multi-ratio bushing current transformer for use with the recloser control and protection functions shall be an integral part of the recloser.

They shall be of class and ratio adequate to ensure they do not saturate under fault conditions up to the full rated interrupting current.

Current transformers shall be thermally rated to the recloser current rating regardless of the ratio selected.

# TS-6.13 Auxiliary Supply

The operating power shall be supplied from an external 240 VAC. A 12Vdc battery with sufficient ampere hour shall be provided for back up control operation in the event of loss of primary supply. The battery shall be capable of operating the control for a minimum of 72 hours. If the primary supply has not been restored within the allowable discharge time of the battery, the control shall automatically shut down. The cable for the external auxiliary supply of approx. 20 m long shall be included in the contract.

# TS-6.14 Control Design Features

The design of the control shall include the following:

- a. Relay Module
- b. CPU Module
- c. Power Supply Module
- d. Communication Interface Module
- e. Front Operating & Display Module
- f. Ethernet/USB/Wi-fi/Fiber Optic/RS 232 Communication Module



The panel includes an LCD that shall allow customizable display for viewing operational data of the control. The LCD shall include complete metering information including all current, voltage and power values along with trip values for all profiles. All modules should be replaceable on site without removing the recloser controller unit.

#### Local Control and Indication

The recloser shall be equipped with the following local operation features through push-buttons operation:

- 1. Trip (with no reclosing)
- 2. Close (Single Shot)
- Auto reclose ON/OFF
- 4. Local remote operation
- 5. View trip Sequences and status information

#### SCADA Operation and Indication

The recloser is required to be controlled and operated using a remote compatible PC with phone modem and applicable software via DNP 3.0 communication protocol.

As a minimum requirement, the following controls and indications shall be provided to the Remote SCADA system using the above protocol:

#### Control and Indication

- Tripping and closing
- Enable and disable automatic sequences (reclosing)
- c. Enable and disable protection
- d. Change protection setting
- e. Reset fault flags and currents
- f. Read and display metering data including a summary page
- g. Read the operation counter
- h. Read the event recorder and display at least 5000 events in time sequence complete with feeder current at the time of the event
- Display a summary page which shows the number of fault trips since it was last reset
- j. Examine recloser/control system malfunction alarms
- k. Read all existing recloser settings
- Switch status (open/close) indications
- Trip sequences and status information i.e., Protective device and sequence which initiated the trip, date and time, Interrupted current, etc.
- m. Buzzer Alarm Trip, Open/Close and Trip Alarm Indications
- n. Hotline Tag should be configurable in the control panel for safety and protection of personnel during off-line maintenance work.



#### TS-6.15 Sequence of Operation

In the event of fault on the line controlled by the recloser, the recloser shall automatically open, and after a minimum dead time, it shall automatically reclose and remain closed should the fault along the line is cleared.

In case the fault persists, the recloser shall again disconnect the line being controlled. The recloser shall be capable of not less than three automatic reclose operations at rated short circuit current should the fault persist and then lock out in the open position until reset by hand or remote control.

If the fault is of a transient in nature, the equipment shall remain closed, and the operating mechanism shall automatically reset.

The number of operations to lockout shall be adjustable in any combination of instantaneous and time-delayed trips up to a minimum of four with a minimum dead time of 0.5 seconds for the first operations.

The Automatic Circuit Recloser shall be mechanically and electrically trip free. Any applied close signal, either mechanically or electrically, shall not inhibit the recloser from tripping on the programmed time-current curve.

Close and trip capacitors shall be used to store the necessary energy for operating the recloser. Only the close capacitor energy shall be used for closing while both capacitors are available for opening. Trip energy shall be available following any electrical close operation.

#### TS-6.16 Protection

The Automatic Circuit Recloser to be supplied shall be equipped with but not limited with the following protections:

- Directional Overcurrent and Earth Fault Protection
- Instantaneous and AC Time Overcurrent Protection
- Under/Over Voltage
- Under/Over Frequency
- Harmonics Protection
- Negative Phase Sequence Protection
- Auto Change Over Protection

All other protections specified in the Technical Data Sheets (TDS).

The controller shall include a sensitive ground/earth fault trip feature that will provide tripping of the recloser after a programmable, definite time for ground currents below normal ground minimum trip levels. The feature shall have a programmable operation to lockout and reclose intervals independent of the ground settings. This feature shall be independently selectable for each protection profile.

A sequence coordination feature shall be included to allow the control to step through selected operation in the operating sequence without tripping.



The control shall include a cold load pick up feature to prevent the control from tripping while energizing non fault system loads.

The Cold Load Pick up feature shall be able to be programmed IN or OUT of service.

#### TS-6.17 Safety Features

The control software shall have a programmable security code to limit access of control programming functions to authorized personnel.

#### TS-6.18 Metering

The control shall provide instantaneous and demand metering with programmable integration intervals for the following minimum functions:

- 1. Real, Reactive and Apparent Power for each phase and total
- 2. Power Factor for each phase and total
- 3. Voltage magnitude for each phase
- 4. Current Magnitude for each phase and neutral
- 5. Positive and Negative Sequence Voltages (magnitude and phase)
- 6. Positive, Negative and Zero Sequence Currents (magnitude and phase)
- 7. Power Quality Monitoring (TDD up 15th Harmonics, HDD Up to 15th Harmonics, Voltage Sags & Swells,)

#### TS-6.19 Event Recorder/Histogram

Event recorder shall be provided to record and store events in a non-volatile memory. The recorder shall include time and date of event and histogram features displays statistical information including tagged min/max values.

#### TS-7.0 SPARES

The Supplier shall furnish a detailed list of required spares for two (2) years operations (if there's any) i.e., protection cards/boards, etc. with equivalent cost.

The list shall include relevant information on the availability and delivery of spare parts.

#### TS-8.0 OTHER TECHNICAL REQUIREMENTS

#### TS-8.1 Operating and Configuration Editor Software Program

Laptop and all software and configuration editor software program including licenses shall be supplied and included in the cost of the equipment in Section IV - Schedule of Requirements of the Terms of Reference. A set of each type of software including licenses plus instruction manuals shall be provided by the Supplier.



All Recloser shall be properly configured, calibrated, and set at factory prior to delivery based on the desired initial pick up current trip setting requirement of each site at present and/or forecasted load data to be provided by SPUG.

#### TS-8.2 Training Requirements

The training requirements shall be as specified in the General Technical Requirements. The number of NPC personnel who will attend overseas training shall be at least three (3). The Supplier shall consider the training in the bid proposal and include in the cost of the equipment.

The Supplier shall provide training in the form of drawing instructions and/or audio visuals.

The training material shall include but not limited to the following topics:

- Handling and Storage
- 2. Application
- 3. Installation, Operation and Maintenance
- 4. Environmental Performance
- 5. Electrical and Mechanical Performance
- 6. Basic Troubleshooting and Disposal

The following subject shall be discussed thoroughly with SPUG End-users and Technical Services Group:

- 1. Basic recloser features and operation
- 2. Field and remote-control operation
- 3. Interrogation for access of event data, recloser status, fault records and metering data
- 4. Fault finding
- 5. Application of protection and control settings/reconfigurations

The Supplier shall also provide local training regarding the proper use and maintenance of the equipment.

#### TS-8.3 Test and Inspection

The Supplier shall provide a test specification covering all tests on the Supplier's premises, successful completion, as deemed by NPC, of Inspection and Tests on Supplier's premises shall be a prerequisite to shipment of all materials, equipment, software or system(s). following successful completion of inspection and tests on his premises, the Supplier shall obtain the approval to proceed with the delivery of the equipment, materials, software or system(s) from NPC in accordance with the Technical Specification for the equipment.

#### **Factory Acceptance and Test**

Prior to shipping and final inspection, Factory Acceptance Test (FAT) shall be conducted by the Supplier at the manufacturer's plant and test results report shall be submitted to NPC.



Each unit shall be completely assembled and adjusted at the factory and perform the manufacturer's Routing, Shop Tests and other tests as specified herein. All parts shall be properly marked for ease of assembly in the field.

Test report on design and routine tests performed in accordance with ANSI/ IEEE and/or IEC standard shall be submitted to NPC for evaluation and approval.

All test certificates shall include the manufacturer's serial number.

#### Type Test

The test to be performed shall be in accordance with the design test set out in Section 6 of ANSI/IEEE C37.60 and Section 5 of ANSI/IEEE C37.63. In addition, the electronic protection /control unit shall have been subject to the relevant impulse, and high frequency noise immunity tests specified in IEC 60255 or equivalent standard.

The recloser complete with control/protection component (including earths) as a composite unit shall have been tested for the rated impulse withstand level and for immunity against the effects of EMI and RFI.

#### **Routine Test**

Routine test shall be carried out and shall be in accordance with the production test set out in Section 7 of ANSI/IEEE C37.60.

#### TS-8.4 Packaging and Marking

#### **Packaging**

The reclosers shall be put in crate individually complete with components i.e. control cubicle, cables, accessories, etc. The equipment must be securely fastened to prevent movement during transport and handling.

The crates must be sufficiently sturdy for another shipping/transportation to SPUG-Palawan various plant sites.

A copy of instruction, operation and maintenance manual for the equipment shall be provided in a weatherproof bag inside each crate.

#### Marking

The following shall be legibly and indelibly marked on two (2) sides of the crate:

- a. Manufacturer:
- b. Contract No./Schedule/Site Delivery
- c. Purchase Items Identification Number
- d. Description of Contents and Gross Mass
- e. Handling or Lifting Instructions



#### TS-9.0 BUS CONDUCTOR AND LINE HARDWARE

#### TS-9.1 Technical Characteristics and Requirements

Describe herein is the general specification of the Bus conductor, line materials and equipment to be supplied for this project.

#### Stranded Conductor

All wires of the stranded conductor shall be concentrically stranded. The wires in each layer shall be evenly and closely stranded around the underlying wire(s). The tension in individual wires in a layer shall be sufficient to hold each wire firmly in place with only enough strand separation to prevent crowding at the time of stranding and during installation. All steel and aluminum wires shall lie naturally in their position in the stranded conductor and, when the core and/or the aluminum wires are cut, the wire ends shall remain in position or be readily replaced by hand and then remain approximately in position.

The aluminum shall be of the higher purity commercially obtainable which shall not be less than 99.5%. The type of conductor to be supplied shall be stated in the Technical Data Sheets and shall be manufactured according to the applicable ASTM or equivalent IEC standards.

The completed conductor shall be smooth, free from nick, burrs, aluminum or steel particles, dirt and excessive die grease. The conductor shall be absolutely free of copper dust and copper particles

#### TS-10.0 ACCEPTANCE CRITERIA

The Supplier shall perform at his own expense all inspection required to ensure adequacy of design, material, workmanship and conformance of the supplied instruments and accessories to the requirements of the specifications and standards.

The equipment/component shall be subjected to the Manufacturer's Standard Factory Tests prior to delivery.

Upon arrival of the instruments and accessories at delivery site, NPC and the Supplier or their authorized representatives, shall jointly verify the instruments and accessories following the steps below:

- a. Inspection and verification of the packing list;
- b. Visual inspection of the condition of the packing and its surfaces; and
- c. Partial opening of the crates/boxes and plastic sheet protection of instrument to verify the content and its physical condition and to check pilferage or damage during shipment and storage.

A record shall be prepared carefully noting all eventual shortages, defects or damages, signed by the Supplier and concurred by NPC. All shortages and damages noted shall be immediately replaced by the Supplier at his own cost



and shall ensure the timely delivery of replacement without affecting the agreed overall contract implementation schedule.

Acceptance certificate shall be issued only upon completion of the following:

- a. The required equipment/component is satisfactorily inspected and delivered to Batag Diesel Power Plant. Inspection result is acceptable to NPC's authorized plant personnel;
- b. Submission of documents as specified hereto in Clause TS-11.0.

If the equipment delivered failed to pass inspection, NPC may at his own judgment, direct the Supplier to make necessary replacement.

#### TS-11.0 DRAWINGS AND DOCUMENTS TO BE SUBMITTED

- a. To be submitted with the bid/proposal for evaluation:
  - a.1 Completely filled-out Technical Data Sheets (TDS);
  - a.2 Original Copy of Manufacturer/Distributor Authorization to Bid, directly addressed to the BAC-NPC, indicating therein the PR/Reference number.

In case of authorized Distributor issuing the authority to bid, it shall be accompanied by a Certificate of Authorized Distributorship from the Manufacturer.

Note: Authorization to bid and Certificate of Distributorship from the Manufacturer shall be current and valid on the date of bid opening as advertised.

- b. To be submitted during post qualification:
  - b.1 Letter of Confirmation from the Manufacturer that a local agent or representative is available to provide "After Sales Service" to the supplied components/parts/accessories during and after the warranty period. Name, address and contact number shall be provided;
  - b.2 Certificate from their customer (End-user) duly addressed to the Bidder that the supplied equipment of the same brand to be offered has performed satisfactorily in service. The certification must indicate in the PR/Reference Number and date of issuance.

Note:

 Authorization to bid shall be current and valid for at least Six (6) months from the date of bid opening as advertised.



- c. To be submitted before or upon delivery:
  - c.1 "Certificate of Origin" from the Manufacturer;
  - c.2 "Warranty Certificate" for one (1) year against factory defects/workmanship;
  - c.3 Outline drawings of Automatic Circuit Recloser and accessories including Schematic and Wiring Diagrams;
  - c.4 User/Instruction and Installation Manual in Three (3) copies;

The instruction manual to be provided shall include the following:

- A schematic diagrams and component layout of all printed circuit boards
- A detailed list of all component and parts including manufacturers part numbers
- A detailed description of the circuit operation including block diagrams
- A comprehensive trouble-shooting guide to assist in faultfinding
- c.5 Manufacturer's Brochures/Catalogues/Drawings which contain information/data to support the Supplier's submitted and filledout Technical Data Sheet;
- c.6 Calibration Certificate Traceable to National/International Standards;
- c.7 Characterization Curve / Calibration Data;
- c.8 Duly signed Routine Test Results; and
- c.9 Field Test to be performed and Certified Test and Inspection Reports duly signed and witnessed by NPC representative.
- Note: All documents in *Clause TS-11.0* shall be submitted to the *Department Manager Visayas Operations Department* for evaluation and/or approval prior to issuance of acceptance certificate.

#### TS-12.0 GUARANTEE

The Supplier shall guarantee to complete the repair, and/or replacement within *Thirty (30) Calendar Days*, of the supplied instruments and accessories at his own expense against defect in design, workmanship and materials for a period of *One (1) Year* after acceptance by NPC. The Supplier must guarantee that the unit will perform in the manner as set forth in the manual and the Contract.

The Supplier shall submit a Warranty Certificate (At Least 1 Year) effective from the date of acceptance by NPC.



PR NO. \$2-BTG22-009

After the lapse of the warranty period, provided that there are no defects found and/or pending repair works, NPC shall release the warranty security/certificate.

#### TS-13.0 MEASUREMENT OF PAYMENT

Payment will be made at the contract unit price for each corresponding item in the Schedule of Requirements. Payment thereof shall constitute the full compensation for the supply, delivery, installation, testing and commissioning of the equipment/component including accessories.



## **SECTION VI - Technical Specifications**

### Part II - Technical Data Sheets

#### **TABLE OF CONTENTS**

SECTION	DESCRIPTION	PAGE
1.0	EQUIPMENT/COMPONENT DATA for the Automatic Circuit Recloser	VI-TDS-1

## **SECTION VI - Technical Specifications**

#### Part II - Technical Data Sheets

# SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15kV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT

- a. The Bidder shall complete this technical data sheet and submit the filled-up form with the technical proposal. The Bidder shall use continuation sheets as necessary for any other additional information keeping to the format shown herein or by reproducing the same.
- b. NPC reserves the right to reject Bids without proper and/or specific data and information as required herein.
- c. The data required are technical features and characteristics of the Equipment/ component/material to be provided by the bidder. Bidder's proposal shall at least be equal or superior to the requirements specified by NPC.

#### 1.0 EQUIPMENT/COMPONENT DATA

Item	Description	NPC 's Requirements	Supplier's Data
AUTO	MATIC CIRCUIT RECLOSER		
1.	Manufacturer	By Supplier	
2.	Place of Manufacture	By Supplier	_
3.	Туре	Solid Dielectric Vacuum Interrupter	
4.	Phase	Three	
5.	Rated Frequency	60 Hz	
6.	Nominal Rated Voltage	13.8 kV	
7.	Maximum Rated Voltage	By Supplier	
8.	Rated Normal Current (Min.)	800 A	
9.	Rated Symmetrical Interrupting Current at rated Voltage	≥12 kA	
10.	Rated Short Time Current for 3 secs.	≥12 kA	
11.	Rated Making Current (RMS)	> 12 kA	
12.	Rated 1 min. power frequency withstand between phase and earth (min.)	50 kV	
13.	Interrupting Medium	Vacuum	
14.	Insulation Medium	Cycloaliphatic epoxy or equivalent	

Name of Bidder:			
Signature of Bidder:			



Item	Description	NPC 's Requirements	Supplier's Data
15.	Rated Operating Sequence (total number of trips/counts to lock out)	4	
16.	Current Sensing	By Supplier	
17.	Voltage Sensing	By Supplier	
18.	Mechanical Life – minimum number of close/open operations – without inspection	30000	
19.	HV Bushing Creepage Distance (min.)	≱465 mm	
20.	Min. length of umbilical (multi- core) cable to be provided	At least 20 m	
21.	AC Supply	230 Volts Single-Phase	
_22	DC Supply		
	a. Voltage	By Supplier	
	b. Make of Batteries	By Supplier	
	с. Туре	Re-chargeable sealed lead-acid battery	
	d. Capacity	By Supplier	
	e. Battery Operating Time after Loss of AC supply	At least 72 hours	
	f. No. of reclose sequences possible within 72 hours after the loss of ac supply	By Supplier	
23.	Spare Battery	Re-chargeable sealed lead-acid battery	
	a. Capacity	26Ah	
	b. Voltage	12Vdc	
	c. Dimensions (LxWxH)	Same as original	
24.	Manual "Open-Close" Functionality with Operator Hook Stick	To be provided	
25.	Controller		
	а. Туре	Electronic type equipped with advance protection, metering, control and communication in an individual module arranged within the compartment	
26.	Protection Features		
	a. Directional Overcurrent     and Earth Fault Protection	Yes	
	b. Instantaneous/Time Overcurrent	Yes	
	c. Sensitive Earth Fault (Current Setting Range 1 – 80 Ampere)	Yes	
	d. Under and Over Voltage	Yes	

Name of Bidder:	
Signature of Bidder:	



PR NO. S2-BTG22-009

Item	Description	NPC 's Requirements	Supplier's Data
	e. Under and Over Frequency (pick-up setting	Yes	
	range of 45 – 65 Hz)		
	f. Cold Load Pick-up Element	Yes	
	g. Inrush Restraint Element	Yes	
	h. Auto Reclosing Element	Yes	
	i. Harmonics Protection Element (Up to 15th Harmonics)	Yes	
	j. Negative Phase Sequence Element	Yes	
	k. Auto Change Over Protection Scheme	Yes	
	Four (4) Independent     Protection Groups     - Each Group must contain     independent protection     settings for each direction	Yes	
27.	Remote control communication of Recloser Controller with integrated free software application and can be installed in a desktop, laptop and cellular phone devices. Effective WIFI signal range minimum of 100ft line of sight	Yes	
_28	Monitoring/Metering Functions	Yes	
29.	Data Records		
	<ul> <li>Sequence of Event (Up to 5000 events can be stored)</li> </ul>	Yes	
	<ul> <li>Fault and Disturbance Records</li> </ul>	Yes	
	c. Load Profile	Yes	
30.	Communication Interface	RS 232/RS 485	
31.	No. of trips to lock-out	Up to 4	
32.	Rated Duty Cycle	O-0.1s CO-1s-CO-1s-CO	
33.	Controller Cubicle Degree of protection	IP 65	
34.	Fault Indicator for overhead lines to be integrated with the control cubicle	To be provided	
35.	Buzzer Alarm Trip, Open/Close Alarm Indications	To be provided	
36.	Bird Guard for insulation protection between the load side and line side, Units	6	
37.	Total Weight, kg	By Supplier	

Name of Bidder:	 
Signature of Bidder:	



Item	Description	NPC 's Requirements	Supplier's Data
	Other Technical Requireme	<u> </u>	
38.	Programming (Configuration) and Maintenance Human- Machine Interface equipped w/ Operating and Configuration Editor Software Program to be provided	Yes	
	a. Type	Laptop Computer	<u> </u>
	No. of Units to be supplied     Hardware	1	
		17/aquivalent of higher	. <u>-</u> .
	1. Processor	17/equivalent of higher	<del></del>
	2. Clock Frequency, GHz	2.0 (min.)	
	RAM Capacity, GB     SSD Drive, Gb	16 512	
<b></b> _		512	
	Hard Disk Capacity, TB     Wideo	Dedicated 4Gb min.	
<u> </u>		Built-in/USB DVD ± RW	<u></u>
	7. Optical Drive		
<del></del>	Display     Audio System	15" LCD Color Monitor	
<del></del>	c. Software	Built-in Stereo Speakers	
	Operating System	Licensed Windows 10Pro, pre- installed with back-up CDROM bundled with latest version of MS Office and reference manuals	
	2. Communication Stack	OSI-TCP / IP	<del></del>
	Configuration Tools	Provided with back-up copy	<u> </u>
	Testing, Maintenance     and Diagnostic Software	Provided with back-up copy	
	d. Peripheral Connectivity		
	Communication Interface (I/O)	USB to Serial Port (RS 232/RS 485) Converter, 2 USB Port, VGA/HDMI/Display/Bizlink Ports, Headphone & Microphone orts and DC jack for power adapter	
	e. Keyboard	84/85 key with embedded numeric key pad	
	f. Mouse	Built-in touch pad pointing device	
	g. Power Adaptor	100 - 240V full range 50 – 60Hz	
	h. Battery	Li-ion battery pack 4-5hrs rundown battery life with APM	

Name of Bidder:	
Signature of Bidder:	

PR NO. S2-BTG22-009


Item	Description	NPC 's Requirements	Supplier's Data
39.	Operating and Configuration Editor Software Program		
	a. All system software and configuration editor software program including licenses and instruction manuals	To be provided	
40.	Training		
	Manufacturer-supervised Hands-on Technical Training including configuration, setting and parameterization	Yes	
	The training requirements shall be provided as specified in Clause TS-8.2	Yes	
	Test and Experience Requirer	ments	
41.	Test Requirement		
	Design and Routine Tests     Reports required	Yes	
42.	Equipment and Manufacturer's Experience		
	The Manufacturer should have been in the business of manufacturing the equipment for not less than:     years <sup>2</sup>	10	
	The same type of equipment being offered should have been in the actual service for not less than: years <sup>2</sup>	5	
43.	Warranty	One (1) year minimum	

#### Notes:

- The Supplier shall place in the filled-in data "submitted" or "will perform" or "had been performed" as appropriate
- Experience less than what is required will be ground for rejection of the equipment being offered.

BUS (	CONDUCTOR		
1.	Manufacturer	By Supplier	
2.	Type designation	Aluminum Conductor Steel Reinforced (ACSR)	
3.	Code Name	By Supplier	
4.	Conductor size	2/0 AWG	
5.	Ampacity, A	270	
6.	Outer Layers		
	a. Material	Aluminum	
	b. Stranding No.	6	
	c. Calculated Cross-sectional Area, mm²	Manufacturer's Data	

Name of Bidder:	<u> </u>	
Signature of Bidder:		
olghalule of blouer.		



PR NO. S2-BTG22-009\_

Ítem	Description	NPC 's Requirements	Supplier's Data_
	d. Coefficient of Elongation (/°C)	Manufacturer's Data	
7.	Core		
	a. Material	Galvanized Steel	_
	b. Stranding No.	1	
	c. Calculated Cross-sectional Area, mm²	Manufacturer's Data	
	d. Coefficient of Elongation (/°C)	Manufacturer's Data	
8.	Conductor Coefficient of Linear Expansion (/°C)	Manufacturer's Data	
	Conductor Hardware		
9.	Connectors		
	а. Туре	wedge pressure clamp for stranded conductor connection	
	b. Angle and T-connectors type	wedge pressure clamp for stranded conductor connection	

Name of Bidder:	
Signature of Bidder:	
. •	



PR NO. S2-BTG22-009

## **SECTION VII**

## **BID PRICE SCHEDULE**

BID DOCUMENTS

SECTION VII - 8ID PRICE SCHEDULE

SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15KV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESELPOWER PLANT PR NO. 52-BTG22-009

#### Section VII - Bid Price Schedule

#### SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15kV AUTOMATIC CIRCUIT RECLOSERS FOR BATAG DIESEL POWER PLANT

				T •	UNIT PRICE FOR GOODS AND RELATED SERVICES TO BE SUPPLIED AND DELIVERED					TOTAL PRICE	
	M NO.	DESCRIPTION	QTY UNIT	C O D E	Unit Price of Goods Delivered up to Philippine Port (Phil. Peso)+	Import Duties & other Levies Imposed by Phil. Govt. (Phil. Peso)	Value Added Tax and other Taxes Imposed by Phil. Govt. (Phil. Peso)	Local Transport from Port to Delivery Site (Phil. Peso)		Local Currency (Phil, Peso) ({E+F+G+H+I} x C)	
	(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(1)	(J)	
_	1 [	Supply, Delivery, and Test of 15kV, 800A, 3 Phase, 60Hz, Automatic Circuit Recloser including Bus Conductors, Line Hardware, and other Accessories in accordance with the Technical Specifications, Technical Data Sheet, and Bid Drawings	1 set			-				7-7	
	2	Dismantling of Existing Automatic Circuit Recloser Including storing to the designated storage facility inside the plant	1 lot								
	_						;				
	_										
									. — —		
				-		·					

•	Bidders shall enter a code representing the Country of Orlgin of all imported
	equipment, materials and accessories

+ Cost of equipment, freight, Insurance, etc. up to Phil. port of entry

Unit Price for Local Transportation, insurance and other local costs incidental to delivery of the goods from the Phil port of entry to final delivery site

Note: Final delivery site of the equipment: Refer to TS-2.0 of the Technical Specifications

Name of Bidder:	
Signature of Bidder:	



Country of Origin

## **SECTION VIII**

## **BIDDING FORMS**



## **SECTION VIII - BIDDING FORMS**

#### **TABLE OF CONTENTS**

NPCSF-GOODS-01	-	Checklist of Technical and Financial Envelope Requirements for Bidders
NPCSF-GOODS-02	-	List of all Ongoing Government & Private Contracts Including Contracts Awarded but not yet Started
NPCSF-GOODS-03	-	Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid
NPCSF-GOODS-04	-	Computation of Net Financial Contracting Capacity (NFCC)
NPCSF-GOODS-05	-	Joint Venture Agreement
NPCSF-GOODS-06a	-	Form of Bid Security : Bank Guarantee
NPCSF-GOODS-06b	-	Form of Bid Security : Surety Bond
NPCSF-GOODS-06c	-	Bid Securing Declaration Form
NPCSF-GOODS-07	-	Omnibus Sworn Statement (Revised)
NPCSF-GOODS-08	-	Bid Letter
Sample Form	-	Bank Guarantee Form for Advance Payment
Sample Form	-	Certification from DTI as Domestic Bidder

#### Checklist of Technical & Financial Envelope Requirements for Bidders

#### A. THE 1ST ENVELOPE (TECHNICAL COMPONENT) SHALL CONTAIN THE FOLLOWING:

- 1. ELIGIBILITY DOCUMENTS
  - a. (CLASS A)
  - Any of the following:
    - PhilGEPS Certificate of Registration and Membership under Platinum Category in accordance with Section 8.5.2 of the IRR:

#### OR:

- The following updated and valid Class "A" eligibility documents enumerated under "Annex A" of the Platinum Membership:
  - Registration Certificate from the Securities and Exchange Commission (SEC) for corporations, Department of Trade and Industry (DTI) for sole proprietorship, or Cooperative Development Authority (CDA) for cooperatives;
  - Mayor's/Business permit issued by the city or municipality where the principal place of business of the prospective bidder is located, or the equivalent document for Exclusive Economic Zones or Areas.
    - In cases of recently expired Mayor's/Business permits, it shall be accepted together with the official receipt as proof that the bidder has applied for renewal within the period prescribed by the concerned local government unit, provided that the renewed permit shall be submitted as a post qualification requirement in accordance with Section 34.2 of the Revised IRR of RA 9184.
  - The prospective bidder's audited financial statements, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "received" by the BIR or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than two (2) years from the date of bid submission.
  - Tax clearance per Executive Order 398, Series of 2005, as finally reviewed and approved by the BIR or as stated under GPPB NPM-039-2014, for Non-Resident Foreign Corporation (NRFC) and Non-Resident Alien Not Engaged in Trade or Business (NRANETB), a Delinquency Verification Certificate may be submitted as a form of Tax Clearance;

#### OR:

- A combination thereof
- Statement of all its ongoing government and private contracts if any, whether similar or not similar in nature and complexity to the contract to be bid (NPCSF-GOODS-02)
- The Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, and whose value, adjusted to current prices using the Philippine Statistics Authority (PSA) consumer price index, must be at least 50% of the ABC (NPCSF-GOODS-03) complete with the following supporting documents:
  - Contract/Purchase Order
  - Certificate of Acceptance; or Certificate of Completion; or Official Receipt (O.R); or Sales Invoice

(The Single Largest Completed Contract (SLCC) as declared by the bidder shall be verified and validated to ascertain such completed contract. Hence, bidders must ensure access to sites of such projects/equipment to NPC representatives for verification and validation purposes during post-qualification process.

It shall be a ground for disqualification, if verification and validation cannot be conducted for reasons attributable to the Bidder.)

Page 1 of 3

➤ Duly signed computation of its Net Financial Contracting Capacity (NFCC) at least equal to the ABC (NPCSF-GOODS-04) or a Committed Line of Credit (CLC) at least equal to ten percent (10%) of the ABC, issued by a Universal or Commercial Bank; If the Bidder opted to submit a Committed Line of Credit (CLC), the bidder must submit a granted credit line valid/effective at the date of bidding.

#### b. (CLASS B)

- For Joint Venture (if applicable), any of the following:
  - Valid Joint Venture Agreement (NPCSF-GOODS-05)

OR

- Notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA, if awarded the contract
- Certification from the relevant government office of their country stating that Filipinos are allowed to participate in their government procurement activities for the same item/product (For foreign bidders claiming eligibility by reason of their country's extension of reciprocal rights to Filipinos)

#### 2. Technical Documents

- Bid Security, any one of the following:
  - Bid Securing Declaration (NPCSF-GOODS-06c)

OR

 Cash or Cashier's/Manager's check issued by a Universal or Commercial Bank -- 2% of ABC;

OR

 Bank draft/guarantee or irrevocable letter of credit issued by a Universal or Commercial Bank: (NPCSF-GOODS-06a) - 2% of ABC;

OR

- Surety Bond callable upon demand issued by a reputable surety or insurance company (NPCSF-GOODS-06b) - 5% of ABC, with
  - Certification from the Insurance Commission as authorized company to issue surety
- Duly signed, completely filled-out and notarized Omnibus Sworn statement (Revised) (NPCSF-GOODS-07), complete with the following attachments:
  - For Sole Proprietorship:
    - Special Power of Attorney
  - For Partnership/Corporation/Cooperative/Joint Venture:
    - Document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)
- Data and Information to be submitted with the Bid/Proposal as specified in Clause TS-11.0(a) of Section VI - Technical Specifications
- Complete eligibility documents of the proposed subcontractor, if any

Page 2 of 3

#### B. THE 2ND ENVELOPE (FINANCIAL COMPONENT) SHALL CONTAIN THE FOLLOWING:

- Duly signed Bid Letter indicating the total bid amount in accordance with the prescribed form (NPCSF-GOODS-08)
- Duly signed and completely filled-out Schedule of Requirement (Section VII) indicating the unit and total prices per item and the total amount in the prescribed Price Schedule form.
- For Domestic Bidder claiming for domestic preference:
  - Letter address to the BAC claiming for preference
  - · Certification from DTI as Domestic Bidder in accordance with the prescribed forms provided

#### **CONDITIONS:**

- Each Bidder shall submit one copy of the first and second components of its Bid. NPC may request additional hard copies and/or electronic copies of the Bid. However, failure of the Bidders to comply with the said request shall not be a ground for disqualification.
- 2. In the case of foreign bidders, the eligibility requirements under Class "A" Documents (except for Tax Clearance) may be substituted by the appropriate equivalent documents, if any, issued by the country of the foreign bidder concerned. The eligibility requirements or statements, the bids, and all other documents to be submitted to the BAC must be in English. If the eligibility requirements or statements, the bids, and all other documents submitted to the BAC are in foreign language other than English, it must be accompanied by a translation of the documents in English. The documents shall be translated by the relevant foreign government agency, the foreign government agency authorized to translate documents, or a registered translator in the foreign bidder's country; and shall be authenticated by the appropriate Philippine foreign service establishment/post or the equivalent office having jurisdiction over the foreign bidder's affairs in the Philippines.
  - These documents shall be accompanied by a Sworn Statement in a form prescribed by the GPPB stating that the documents submitted are complete and authentic copies of the original, and all statements and information provided therein are true and correct. Upon receipt of the said documents, the PhilGEPS shall process the same in accordance with the guidelines on the Government of the Philippines -- Official Merchants Registry (GoP-OMR).
- A Bidder not submitting bid for reason that his cost estimate is higher than the ABC, is required to submit his letter of non-participation/regret supported by corresponding detailed estimates. Failure to submit the two (2) documents shall be understood as acts that tend to defeat the purpose of public bidding without valid reason as stated under Section 69.1.(i) of the revised IRR of R.A. 9184.

PR NO. S2-BTG22-009

Standard Form Number: NPCSF-GOODS-02

#### List of All Ongoing Government and Private Contracts Including Contract Awarded But Not Yet Started

Business Name : Business Address :						
	-		Bidder's Rot	e	a. Date Awarded	
Name of Contract/ Project Cost	a. Owner's Name b. Address c. Telephone Nos.	Nature of Work	Description	%	b. Date Started c. Date of Completion or Contract Duration/ Date of Delivery	Value of Outstanding Works / Undelivered Portion
Government						
		-				
•••				<del> </del>		
Private				<del> </del>		
T. vato			<del> </del>	<del>                                     </del>	*	
					-	
				<del> </del>	<del> </del>	
					Total Cost	
		<del>-</del>				

The bidder shall declare in this form all his on-going government and private contracts including contracts where the bidder (either as individual or as a Joint Venture) is a partner in a Joint Venture agreement other than his current joint venture where he is a partner. Non declaration will be a ground for disqualification of bid.

Note: This statement shall be supported with the following documents for all the contract(s) stated above which shall be submitted during Post-qualification:

- 1. Contract/Purchase Order and/or Notice of Award
- 2. Certification coming from the project owner/client that the performance is satisfactory as of the bidding date.

Submitted by	: <u> </u>	
	_	(Printed Name & Signature)
Designation	: _	
Date	: _	

Submitted by

Designation Date (Printed Name & Signature)

SECTION VIII - BIDDING FORMS

SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15KV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT

PR NO. S2-BTG22-009

Standard Form Number: NPCSF-GOODS-03

iness Name : iness Address :	·· <del>·</del>					
	a Oumada Nama		Contractor's R	Role		- D
Name of Contract	a. Owner's Name b. Address c. Telephone Nos.	Nature of Work	Description	%	a.Amount at Award b.Amount at Completion c. Duration	a. Date Awarded b. Contract Effectivit c. Date Completed

## **NET FINANCIAL CONTRACTING CAPACITY (NFCC)**

Α.	Summary of the Supplier's/Distributor's/Manufacturer's assets and liabilities on the basis
	of the income tax return and audited financial statement for the immediately preceding
	calendar year are:

		Year 20
1.	Total Assets	
2.	Current Assets	
3.	Total Liabilities	
4.	Current Liabilities	
5.	Net Worth (1-3)	
6.	Net Working Capital (2-4)	

B.	The Net Financial Contracting Capacity (NFCC) based on the above data is computed as follows:
	NFCC = [(Current assets minus current liabilities) x 15] minus the value of all outstanding or uncompleted portions of the projects under ongoing contracts, including awarded contracts yet to be started coinciding with the contract for this Project.

NFCC = P		
111 00 1		

Herewith attached is certified true copy of the audited financial statement, stamped "RECEIVED" by the BIR or BIR authorized collecting agent for the immediately preceding calendar year.

Submitted by:
Name of Supplier / Distributor / Manufacturer
Signature of Authorized Representative
Date :

SECTION VIII - BIDDING FORMS

Standard Form Number: NPCSF-GOODS-05

#### **JOINT VENTURE AGREEMENT**

KNO	OW AL	F WEN B.	Y THESE PRESENTS:						
That				(civil status,	entered into by and between: , authorized representative of				
				- and –					
_			, of legal age, <u>{c</u> a resident of	ivil status <u>)</u>	, authorized representative of				
	urces a	nd efforts	ties agree to join toge to enable the Joint Ver Contract of the <b>Nation</b> a	ture to partic	pital, manpower, equipment, and other cipate in the Bidding and Undertaking of rporation.				
		NAME	OF PROJECT		CONTRACT AMOUNT				
	Tha	t the capit	al contribution of each r	nember firm:					
		NAME	OF FIRM		CAPITAL CONTRIBUTION				
1				₽					
2.			<u> </u>	P					
	ling and	Undertak	ing of the said contract.		ally liable for their participation in the				
	Tha	t both par	ties agree that		and/or shall are granted full power and authority to				
do, e Bidd do a	execute ling and nd if pe Tha	and perfollondertalersonally points to this Join	orm any and all acts ne- sing of the said contract resent with full power of	cessary and , as fully an substitution	or to represent the Joint Venture in the defectively and the Joint Venture may				
-	Name	e & Signat	ure of Authorized		Name & Signature of				
Representative					Authorized Representative				
•		Official E	Designation		Official Designation				
-		Name	of Firm		Name of Firm				
			W	litnesses					
1.				2					

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

SECTION VIII - BIDDING FORMS

Standard Form Number: NPCSF-GOODS-06a

## FORM OF BID SECURITY (BANK GUARANTEE)

WHEREAS, (Name of Bidder) (hereinafter called "the Bidder") has submitted his bid dated (Date) for the [name of project] (hereinafter called "the Bid").
KNOW ALL MEN by these presents that We (Name of Bank)  (Name of Country)  having our registered office at (hereinafter called "the Bank" are bound unto National Power Corporation (hereinafter called "the Entity") in the sum of [amount in words & figures as prescribed in the bidding documents] for which payment well and truly to be made to the said Entity the Bank binds himself, his successors and assigns by these presents.
SEALED with the Common Seal of the said Bank this day of 20
THE CONDITIONS of this obligation are that:
<ol> <li>if the Bidder withdraws his Bid during the period of bid validity specified in the Biddin Documents; or</li> </ol>
<ol> <li>if the Bidder does not accept the correction of arithmetical errors of his bid price i accordance with the Instructions to Bidder; or</li> </ol>
<ol> <li>if the Bidder, having determined as the LCB, fails or refuses to submit the required ta clearance, latest income and business tax returns and PhilGEPs registration certificat within the prescribed period; or</li> </ol>
4) if the Bidder having been notified of the acceptance of his bid and award of contract t him by the Entity during the period of bid validity:
a) fails or refuses to execute the Contract; or
b) fails or refuses to submit the required valid JVA, if applicable; or
<ul> <li>c) fails or refuses to furnish the Performance Security in accordance with th Instructions to Bidders;</li> </ul>
we undertake to pay to the Entity up to the above amount upon receipt of his first writte demand, without the Entity having to substantiate its demand, provided that in his demand th Entity will note that the amount claimed by it is due to the occurrence of any one or combinatio of the four (4) conditions stated above.
The Guarantee will remain in force up to 120 days after the opening of bids or as it may be extended by the Entity, notice of which extension(s) to the Bank is hereby waived. Any deman in respect of this Guarantee should reach the Bank not later than the above date.
DATE SIGNATURE OF THE BANK
WITNESS SEAL
(Signature, Name and Address)

SECTION VIII - BIDDING FORIVIS

a)

b)

Employer.

Standard Form Number: NPCSF-GOODS-06b

FORM OF BID SECURITY (SURETY BOND)
BOND NO.: DATE BOND EXECUTED:
By this bond, We ( <u>Name of Bidder</u> ) (hereinafter called "the Principal") and ( <u>Name of Surety</u> ) of ( <u>Name of Country of Surety</u> ), authorized to transact business in the Philippines (hereinafter called "the Surety") are held and firmly bound unto National Power Corporation (hereinafter called "the Employer") as Obligee, in the sum of ( <u>amount in words &amp; figures as prescribed in the bidding documents</u> ), callable on demand, for the payment of which sum, well and truly to be made, we, the said Principal and Surety bind ourselves, our successors and assigns, jointly and severally, firmly by these presents.
SEALED with our seals and dated this day of 20
WHEREAS, the Principal has submitted a written Bid to the Employer dated the day of 20, for the (hereinafter called "the Bid").
NOW, THEREFORE, the conditions of this obligation are:
<ol> <li>if the Bidder withdraws his Bid during the period of bid validity specified in the Bidding Documents; or</li> </ol>
<ol> <li>if the Bidder does not accept the correction of arithmetical errors of his bid price in accordance with the Instructions to Bidder; or</li> </ol>
<ol> <li>if the Bidder, having determined as the LCB, fails or refuses to submit the required tax clearance, latest income and business tax returns and PhilGEPs registration certificate within the prescribed period; or</li> </ol>
4) if the Bidder having been notified of the acceptance of his bid and award of contract to him by the Entity during the period of bid validity:
d) fails or refuses to execute the Contract; or
e) fails or refuses to submit the required valid JVA, if applicable; or
<ul> <li>f) fails or refuses to furnish the Performance Security in accordance with the Instructions to Bidders;</li> </ul>
then this obligation shall remain in full force and effect, otherwise it shall be null and void.
PROVIDED HOWEVER, that the Surety shall not be:

liable for a greater sum than the specified penalty of this bond, nor

liable for a greater sum that the difference between the amount of the said Principal's Bid and the amount of the Bid that is accepted by the

SECTION VIII - BIDDING FORMS

Standard Form Number: NPCSF-GOODS-06b Page 2 of 2

This Surety executing this instrument hereby agrees that its obligation shall be valid for 120 calendar days after the deadline for submission of Bids as such deadline is stated in the Instructions to Bidders or as it may be extended by the Employer, notice of which extension(s) to the Surety is hereby waived.

PRINCIPAL	SURETY
SIGNATURE(S)	SIGNATURES(S)
NAME(S) AND TITLE(S)	NAME(S)
SEAL	SEAL

SECTION VIII - BIDDING FORMS

Standard Form No: NPCSF-GOODS-06c

REPUBLIC OF THE PHILIPPINES )	
CITY OF	) S.S

#### **BID-SECURING DECLARATION**

SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15KV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT (PR NO. \$2-BTG22-009)

To: National Power Corporation BIR Road cor. Quezon Ave. Diliman, Quezon City

I/We<sup>1</sup>, the undersigned, declare that:

- 1. I/We understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid-Securing Declaration.
- 2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by the Procuring Entity for the commission of acts resulting to the enforcement of the Bid Securing Declaration under Sections 23.1 (b), 34.2, 40.1 and 69.1, except 69.1 (f) of the IRR of R.A. 9184; without prejudice to other legal action the government may undertake.
- 3. I/We understand that this Bid-Securing Declaration shall cease to be valid on the following circumstances:
  - (a) Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
  - (b) I am/we are declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I/we failed to timely file a request for reconsideration or (ii) I/we filed a waiver to avail of said right;
  - (c) I am/we are declared as the bidder with the Lowest Calculated and Responsive Bid, and I/we have furnished the performance security and signed the Contract.

20at, Philippines.	have hereunto set my hand this day of
	[Name and Signature of Bidder's Representative/ Authorized Signatory] [Signatory's legal capacity] Affiant

[Jurat]
[Format shall be based on the latest Rules on Notarial Practice]

I Select one and delete the other. Adopt same instruction for similar terms throughout the document.

-----

Standard Form No: NPCSF-GOODS-07

#### **Omnibus Sworn Statement (Revised)**

REPUBLIC	OF	THE	<b>PHILIF</b>	PINES	)
CITY/MUNI	CIP	ALIT	Y OF	)	S.S

#### **AFFIDAVIT**

- I, [Name of Affiant], of legal age, [Civil Status], [Nationality], and residing at [Address of Affiant], after having been duly sworn in accordance with law, do hereby depose and state that:
- 1. [Select one, delete the other:]

[If a sole proprietorship:] I am the sole proprietor or authorized representative of [Name of Bidder] with office address at [address of Bidder];

[If a partnership, corporation, cooperative, or joint venture:] I am the duly authorized and designated representative of [Name of Bidder] with office address at [address of Bidder];

2. [Select one, delete the other:]

[If a sole proprietorship:] As the owner and sole proprietor, or authorized representative of [Name of Bidder], I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached duly notarized Special Power of Attorney;

[If a partnership, corporation, cooperative, or joint venture:] I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable;)];

- 3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;
- Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
- 5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
- 6. [Select one, delete the rest:]

[If a sole proprietorship:] The owner or sole proprietor is not related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a partnership or cooperative:] None of the officers and members of [Name of Bidder] is related to the Head of the Procuring Entity, members of the Bids and Awards Committee

SECTION VIII - BIDDING FORMS

(BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a corporation or joint venture:] None of the officers, directors, and controlling stockholders of [Name of Bidder] is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

- 7. [Name of Bidder] complies with existing labor laws and standards; and
- 8. [Name of Bidder] is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:
  - Carefully examining all of the Bidding Documents;
  - b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
  - Making an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the [Name of the Project].
- [Name of Bidder] did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.
- 10. In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.

IN	WITNESS	WHEREOF,	-	have	hereunto	set	my	hand	this		day	of	20	at
		, Philippines.					•			_	•			

[Insert NAME OF BIDDER OR ITS AUTHORIZED REPRESENTATIVE] [Insert signatory's legal capacity] Affiant

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

#### **BID LETTER** Date: THE PRESIDENT To: National Power Corporation BIR Road cor, Quezon Ave. Diliman, Quezon City Gentlemen: Having examined the Bidding Documents including Bid Bulletin Numbers finsert , the receipt of which is hereby duly acknowledged, we, the undersigned, offer to perform SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF 15KV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT ( \$2-BTG22-009) in conformity with the said Bidding Documents for the sum of [total Bid amount in words and \_\_\_ or such other sums as may be ascertained in accordance with the Schedule of Prices attached herewith and made part of this Bid. We undertake, if our Bid is accepted, to supply and deliver the goods and perform other services, if required within the contract duration and in accordance with the scope of the contract specified in the Schedule of Requirements and Technical Specifications. If our Bid is accepted, we undertake to provide a performance security in the form, amounts, and within the times specified in the Bidding Documents. We agree to abide by this Bid for the Bid Validity Period specified in Bid Documents and it shall remain binding upon us and may be accepted at any time before the expiration of that period. Until a formal Contract is prepared and executed, this Bid, together with your written acceptance thereof and your Notice of Award, shall be binding upon us. We understand that you are not bound to accept the Lowest Calculated Bid or any Bid you may receive. We certify/confirm that we comply with the eligibility requirements pursuant to the Bidding Documents. We likewise certify/confirm that the undersigned, (for sole proprietorships, insert: as the owner and sole proprietor or authorized representative of [Name of Bidder] has the full power and authority to participate, submit the bid, and to sign and execute the ensuing contract, on the latter's behalf for the [Name of Project] \_ of the National Power Corporation for partnerships, corporations, cooperatives, or joint ventures, insert: is granted full power and authority by the [Name of Bidder] to participate, submit the bid, and to sign and execute the ensuing contract on the latter's behalf for [Name of Project] of the National Power Corporation. We acknowledge that failure to sign each and every page of this Bid Letter, including the attached Schedule of Requirements (Bid Price Schedule), shall be a ground for the rejection of our bid. fin the capacity of) [name and signature of authorized signatory]

[name of bidder]

Duly authorized to sign Bid for and on behalf of \_\_\_\_\_

#### **Bank Guarantee Form for Advance Payment**

To: THE PRESIDENT

National Power Corporation BIR Road cor. Quezon Ave. Diliman, Quezon City

[name of Contract]

#### Gentlemen and/or Ladies:

In accordance with the Advance Payment Provision, of the General Conditions of Contract, <u>[name and address of Supplier]</u> (hereinafter called the "Supplier") shall deposit with the PROCURING ENTITY a bank guarantee to guarantee its proper and faithful performance under the said Clause of the Contract in an amount of <u>[amount of guarantee in figures and words]</u>.

We, the <u>fname of the universal/commercial bankl</u>, as instructed by the Supplier, agree unconditionally and irrevocably to guarantee as primary obligator and not as surety merely, the payment to the PROCURING ENTITY on its first demand without whatsoever right of objection on our part and without its first claim to the Supplier, in the amount not exceeding <u>famount of guarantee in figures and words</u>].

We further agree that no change or addition to or other modification of the terms of the Contract to be performed thereunder or of any of the Contract documents which may be made between the PROCURING ENTITY and the Supplier, shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition, or modification.

This guarantee shall remain valid and in full effect from the date the advance payment is received by the Supplier under the Contract and until the Goods are accepted by the PROCURING ENTITY.

Yours truly,

[name of bank or financial institution]						
[address]						
[date]	<del></del>					

Signature and seal of the Guarantors

#### <del>----</del>-----

## **CERTIFICATION AS A DOMESTIC BIDDER**

This is to certify that based on the records of this c	office, (Name of Bidder) is
duly registered with the DTI on	
This further certifies that the articles forming part of	of the product of (Name of Bidder).
which are/is (Specify)	are substantially composed of
articles, materials, or supplies grown, produced or mar	nufactured in the Philippines. (Please
encircle the applicable description/s).	
This certification is issued upon the request of (Nar	me of Person/Entity) in
connection with his intention to participate in the bidding	for the (Name of Project)
of the National Power Corporation (NPC).	
Given this day of 20 at	, Philippines
	Name
	Position
	Department of Trade & Industry

## **SECTION IX**

## **BID DRAWINGS**



PR NO. \$2-BTG22-009


#### **SECTION IX - BID DRAWINGS**

#### **EW - ELECTRICAL DRAWINGS**

DRAWING NO. TITLE

BtgDPP-BDE-17.001 Single Line Diagram

BtgDPP-BDE-17.002 Details of Take-off Structure



RÉV. DATE

NATURE OF REVISION

#### NOTES:

- ALL EQUIPMENT TO BE SUPPLIED SHALL BE TESTED AND PROVEN PASSED IN ACCORDANCE TO THE REQUIREMENTS OF SECTION VI. TECHNICAL SPECIFICATIONS.
- 2. ALL EQUIPMENT IN THE SHADED AREA ARE EXISTING.
- ALL EQUIPMENT DRAWN IN HIDDEN LINES ARE FOR FUTURE INSTALLATION. ALL OTHERS ARE INCLUDED IN THE CONTRACT.

### LEGEND:



15kV, 800A, AUTOMATIC CIRCUIT RECLOSER



#### NATIONAL POWER CORPORATION AGHAM ROAD, DILIMAN, QUEZON CITY

PROJECT: SUPPLY, DELIVERY, INSTALLATION, TEST AND COMMISSIONING OF 15kV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT

LOCATION: Brgy. Marubay, Laoang, Northern Samar

TITLE

BY CHKD. RECD. APPD.


#### SINGLE LINE DIAGRAM


!				1 ()//
	BY	CHKD	DATE	Tensel 140
DESIGNED	N.			SUBMITTED: R.F. VERAR
DRAWN	<b>₹</b>			9ffficibal Engineer
REVIEWED	PRINCIPAL ENG'R. / ARCH'T.			RECOMMENDED C. Z. C. LUGOD JR.
CIVILLARCHT				Manager GEICD
ELEÇ.				APPROVED: N.G. SOTA SERRA
MECH.			l	Manager, DDD

DWG. NO. BtgDPP-BDE-17.001 | P.R. NO. \$2-BTG22-009

**BID DRAWING** SCALE: N.T.S.

REV. 0





#### **SECTION A-A**

REV. DATE

#### NOTES:

- ALL EQUIPMENT/STRUCTURES DRAWN IN HIDDEN LINES ARE EXISTING. ALL OTHERS ARE INCLUDED IN THE CONTRACT.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE WITH ALL DAMAGES OCCURRED DURING THE DISMANTLING AND INSTALLATION WORKS. ALL DAMAGED EQUIPMENT SHALL BE REPLACED BY THE SUPPLIER AT NO ADDITIONAL COST TO NPC.



#### NATIONAL POWER CORPORATION AGHAM ROAD, DILIMAN, QUEZON CITY

PROJECT: SUPPLY, DELIVERY, INSTALLATION, TEST AND COMMISSIONING OF 15kV AUTOMATIC CIRCUIT RECLOSER FOR BATAG DIESEL POWER PLANT

LOCATION: 8rgy, Marubay, Lacang, Northern Samar

### **DETAILS OF TAKE-OFF STRUCTURE**

BY	CHXD	DATE		HILLAND
٨			SUBMITTED:	R/P. VERAR
<b>₩</b>				Pancipal Engineer A
PRINCIPAL ENGIR, / ARCHT.			RECOMMENDE	C.Z.C.LUGOD JR.
			] `	Manager, AEICO
			APPROVED:	N. G. SOMOSIERRA-
			]	Manager, DDD
	A			SUBMITTED:

DWG.NO. BtgDPP-BDE-17.002 P.R.NO. S2-BTG22-009

**BID DRAWING** 

REV. 0

SCALE: N.T.S. BY CHKD. RECO. APPD. NATURE OF REVISION